South Texas College Board of Trustees Facilities Committee Ann Richards Administration Building, Board Room Pecan Campus Tuesday, October 6, 2015 @ 3:00 PM McAllen, Texas

"At anytime during the course of this meeting, the Board of Trustees may retire to Executive Session under Texas Government Code 551.071(2) to confer with its legal counsel on any subject matter on this agenda in which the duty of the attorney to the Board of Trustees under the Texas Disciplinary Rules of Professional Conduct of the State Bar of Texas clearly conflicts with Chapter 551 of the Texas Government Code. Further, at anytime during the course of this meeting, the Board of Trustees may retire to Executive Session to deliberate on any subject slated for discussion at this meeting, as may be permitted under one or more of the exceptions to the Open Meetings Act set forth in Title 5, Subtitle A, Chapter 551, Subchapter D of the Texas Government Code."

l.	Approval of September 10, 2015 Facilities Committee Meeting Minutes1-11
II.	Update on Status of 2013 Bond Construction Program
III.	Review and Recommend Action on Vendor Reference Process for Request for Construction Proposals and Request for Qualifications
IV.	Review and Recommend Action on Solicitation of Request for Proposals (RFP) for Owner Procurement of Thermal Energy Plant Chillers for 2013 Bond Construction Projects
V.	Review and Recommend Action on Contracting Mechanical, Electrical, Plumbing, (MEP) Engineering Services for the Nursing and Allied Health Campus Thermal Plant
VI.	Review and Recommend Action to Incorporate the Redesign and Renovation of the Existing Library Building with the 2013 Bond Construction Mid Valley Campus Library Expansion Project
VII.	Review and Recommend Action on Increased Design Services for Mata Garcia Architects to Incorporate the Redesign of the Existing Library Building with the 2013 Bond Construction Mid Valley Campus Library Expansion Project
VIII.	Review and Recommend Action on Schematic Design of the 2013 Bond Construction Mid Valley Campus Parking and Site Improvements44-51
IX.	Review and Recommend Action on Schematic Design of the 2013 Bond Construction Technology Campus Parking and Site Improvements
Χ.	Review and Recommend Action on Schematic Design of the 2013 Bond Construction Nursing & Allied Health Campus Parking and Site Improvements
XI.	Review and Recommend Action on Update for Schematic Design of the 2013 Bond Construction Exterior Elevations of the Pecan Campus South Academic Building

Facilities Committee Meeting
October 6, 2015 @ 3:00 p.m.
Agenda

XII.	Review and Recommend Action on Update for Schematic Design of the 2013 Bond Construction Exterior Elevations of the Pecan Campus STEM Building
XIII.	Review and Recommend Action on Contracting Civil Engineering Services for the Non-Bond Pecan Plaza Parking Area for Police Vehicles
XIV.	Review and Recommend Action on Schematic Design of the Non-Bond Pecan Campus Student Support Services Building K Student Enrollment Center 94-103
XV.	Review and Recommend Action on Approval of Change Order for the Non-Bond Pecan Campus Portable Buildings Infrastructure
XVI.	Review and Recommend Action on Substantial or Final Completion for the Following Non-Bond Construction Projects
XVII.	Update on Status of Non-Bond Construction Projects110-114

Motions October 6, 2015 Page 1, 10/2/2015 @ 9:04 AM

Approval of September 10, 2015 Facilities Committee Meeting Minutes

The Minutes for the Facilities Committee meeting of September 10, 2015 are presented for Committee approval.

South Texas College
Board of Trustees
Facilities Committee
Ann Richards Administration Building, Board Room
Pecan Campus
Thursday, September 10, 2015
@ 3:00 PM
McAllen, Texas

MINUTES

The Facilities Committee Meeting was held on Tuesday, August 25, 2015 in the Ann Richards Administration Building Board Room at the Pecan Campus in McAllen, Texas. The meeting commenced at 3:22 p.m. with Mr. Gary Gurwitz presiding.

Members present: Mr. Gary Gurwitz, Dr. Alejo Salinas, Jr., Mr. Paul R. Rodriguez, Ms. Rose Benavidez, and Mrs. Graciela Farias

Members absent: Mr. Roy de León and Mr. Jesse Villarreal

Also present: Dr. Shirley A. Reed, Mr. Chuy Ramirez, Mrs. Mary Elizondo, Mrs. Wanda Garza, Mr. Ricardo de la Garza, Mr. Robert Cuellar, Mr. Fernando Lamas, Mr. Ali Kolahdouz, Mr. Victor Gonzalez, Mr. Gilbert Gallegos, Mr. Rolando Garcia, Ms. Diana Bravos, Mr. Ramiro Gutierrez, Mr. Trey Murray, and Mr. Andrew Fish

Approval of August 11, 2015 Facilities Committee Meeting Minutes

Upon a motion by Mr. Paul R. Rodriguez and a second by Ms. Rose Benavidez, the Minutes for the Facilities Committee meeting of August 11, 2015 were approved as written. The motion carried.

Approval of August 25, 2015 Facilities Committee Meeting Minutes

Upon a motion by Mr. Paul R. Rodriguez and a second by Mrs. Graciela Farias, the Minutes for the Facilities Committee meeting of August 25, 2015 were approved as written. The motion carried.

Update on Status of 2013 Bond Construction Program

The packet included a copy of the presentation prepared by Broaddus & Associates as an update on the status of the 2013 Bond Construction Program. Mr. Gilbert Gallegos from Broaddus & Associates attended the September 10, 2015 Board Facilities Committee meeting to provide the update.

Review and Recommend Action on Schematic Design of the 2013 Bond Construction Mid Valley Campus Thermal Plant

Approval of schematic design by DBR Engineering for the 2013 Bond Construction Mid Valley Campus Thermal Plant will be requested at the September 22, 2015 Board meeting.

Purpose

Schematic design is the first phase of basic design services provided by the project design team. In this phase, the design team prepares schematic drawings based on the Owner's project program and design meetings with staff. The approval of this phase is necessary to establish the basis on which the project design team is given authorization to proceed with design development and construction document phases.

Justification

Once schematic design is approved, DBR Engineering will proceed to prepare all necessary design development drawings and specifications in preparation for the construction documents phase using STC design standards as well as all applicable codes and ordinances. The phases of a construction project are as follows: 1.) Schematic Design, 2.) Design Development, 3.) Construction Documents, 4.) Guaranteed Maximum Price, 5.) Construction, and 6.) Closeout

The Construction Manager-at-Risk provides preconstruction services during the design processes leading to the construction phase. A Guaranteed Maximum Price (GMP) will then be developed and will be presented to the Facilities Committee for review at a future date.

Background

As previously authorized by the Board of Trustees, DBR Engineering began working with Broaddus & Associates, Facilities Planning & Construction, and STC staff to develop plans and elevations. The proposed Mid Valley Campus Thermal Plant project was part of the 2013 Bond Construction Program and included the following scope:

> Engineer

DBR Engineering

> Construction Manager-at-Risk

- Skanska Building USA
- Construction Cost Limitation (CCL)
 - \$3,800,000

Program Scope

- SQ FT 3,888
- One Floor

Chillers and Mechanical Support

- Water cooled chillers (4 at 600 tons each)
- Office Spaces
 - o Facility Manager
 - Office Pool
 - Inventory/Custodial
- Building Support Spaces
 - o Restroom
 - Loading Areas

Funding Source

The current Construction Cost Limitation (CCL) was \$3,800,000 and would be adjusted once the Guaranteed Maximum Price (GMP) proposals were submitted by the Construction Manager-at-Risk to be presented to the Board for approval. Bond funds were budgeted in the Bond Construction budget for fiscal year 2015-2016.

Reviewers

The proposed schematic design was reviewed by Broaddus & Associates and staff from Facilities Planning & Construction, Operations and Maintenance, Administration, and Technology Resources departments.

Enclosed Documents

DBR Engineering developed a schematic presentation describing the proposed design. The packet included drawings of the site plan, floor plans, and exterior views.

Presenters

DBR Engineering developed a schematic presentation describing the proposed design. Representatives from Broaddus & Associates and DBR Engineering attended the Facilities Committee meeting to present the schematic design of the proposed expansion project.

Upon a motion by Mr. Gary Gurwitz and a second by Mrs. Graciela Farias, the Facilities Committee recommended Board approval of the proposed schematic design by DBR Engineering for the 2013 Bond Construction Mid Valley Campus Thermal Plant as presented. The motion carried.

Review and Recommend Action on Schematic Design of the 2013 Bond Construction Starr County Campus Thermal Plant

Approval of schematic design by Sigma HN Engineers for the 2013 Bond Construction Starr County Campus Thermal Plant will be requested at the September 22, 2015 Board meeting.

Purpose

Schematic design is the first phase of basic design services provided by the project design team. In this phase, the design team prepares schematic drawings based on the Owner's project program and design meetings with staff. The approval of this phase is necessary to establish the basis on which the project design team is given authorization to proceed with design development and construction document phases.

Justification

Once schematic design is approved, Sigma HN Engineers will proceed to prepare all necessary design development drawings and specifications in preparation for the construction documents phase using STC design standards as well as all applicable codes and ordinances. The phases of a construction project are as follows: 1.) Schematic Design, 2.) Design Development, 3.) Construction Documents, 4.) Guaranteed Maximum Price, 5.) Construction, and 6.) Closeout

The Construction Manager-at-Risk provides preconstruction services during the design processes leading to the construction phase. A Guaranteed Maximum Price (GMP) will then be developed and will be presented to the Facilities Committee for review at a future date.

Background

As previously authorized by the Board of Trustees, Sigma HN Engineers began working with Broaddus & Associates, Facilities Planning & Construction, and STC staff to develop plans and elevations. The proposed Starr County Campus Thermal Plant project was part of the 2013 Bond Construction Program and included the following scope:

- > Engineer
 - Sigma HN Engineers
- Construction Manager-at-Risk
 - D. Wilson Construction
- Construction Cost Limitation (CCL)
 - \$3,800,000
- Program Scope
 - SQ FT 4.082
 - One Floor

- Chillers and Mechanical Support
 - Water cooled chillers (3 @ 400 tons each)
- Chiller Equipment Space
- Office Spaces
 - o Facility Manager
 - Office Pool
 - Inventory/Custodial
- Building Support Spaces
 - o Restroom
 - Loading Area

Funding Source

The current Construction Cost Limitation (CCL) was \$3,800,000 and would be adjusted once the Guaranteed Maximum Price (GMP) proposals were submitted by the Construction Manager-at-Risk to be presented to the Board for approval. Bond funds were budgeted in the Bond Construction budget for fiscal year 2015-2016.

Reviewers

The proposed schematic design was reviewed by Broaddus & Associates and staff from Facilities Planning & Construction, Operations and Maintenance, Administration, and Technology Resources departments.

Enclosed Documents

Sigma HN Engineers developed a schematic presentation describing the proposed design. The packet included drawings of the site plan, floor plans, and exterior views.

Presenters

Sigma HN Engineers developed a schematic presentation describing the proposed design. Representatives from Broaddus & Associates and Sigma HN Engineers will be present at the Facilities Committee meeting to present the schematic design of the proposed expansion project.

Upon a motion by Ms. Rose Benavidez and a second by Mrs. Graciela Farias, the Facilities Committee recommended Board approval of the proposed schematic design by Sigma HN Engineers for the 2013 Bond Construction Starr County Campus Thermal Plant as presented. The motion carried.

Review and Recommend Action to Incorporate the Redesign and Renovation of the Existing Library Building with the 2013 Bond Construction Mid Valley Campus Program Library Expansion Project

Approval to incorporate the redesign and renovation of the existing library building with the 2013 Bond Construction Mid Valley Campus Library Expansion project will be requested at the September 22, 2015 Board meeting.

Purpose

Authorization was requested to incorporate the redesign and renovation of the existing library building with the 2013 Bond Construction Mid Valley Campus Library Expansion project will be discussed.

Justification

The 2013 Bond Program included an expansion to the existing Mid Valley Campus Library. Incorporating the redesign and renovation of the existing library space with the design of the 2013 Bond Construction Mid Valley Campus Library Expansion project, would ensure that the entire building is designed to function properly and provide the necessary library services effectively for the students. The design of the entire library space would allow for future planning, coordination of temporary library services, cost estimating, and scheduling for the construction of the existing library space.

Background

The existing library at the Mid Valley Campus consisted of 24,000 square feet. An expansion of approximately 10,000 square feet was scheduled to be constructed as part of the 2013 Bond Construction Program. The concurrent redesign and renovation of the current library space with the designing and construction of the new library expansion was recommended to allow the existing and new portions of the building to function as a cohesive whole.

As previously authorized by the Board of Trustees, Mata+Garcia Architects began working with Broaddus & Associates, Facilities Planning & Construction, and STC staff to develop the schematic design for the 2013 Bond Construction Mid Valley Campus Library Expansion. As an additional service to Mata+Garcia Architect's contract, 720 Design, Inc. was authorized to provide an interior library design concept plan for the new library expansion as well as for the existing library building.

Feedback to staff was requested on how to proceed with the recommendation of the concurrent design and construction of the two spaces. An option was to expand the scope for the architect and Construction Manager-at-Risk contractor awarded the 2013 Bond Construction Mid Valley Campus Library Expansion project with the redesign and renovation of the existing library space.

Funding Source

Funds would be identified depending on the course of action. Possible options for consideration were:

- Funds may be identified to be budgeted in the non-bond construction budget for FY 2016-2017.
- Funds may be identified by reallocating project funds in the approved non-bond construction budget for FY 2015-2016.
- Funds may be available from possible bond construction project savings in FY 2015-2016 and/or FY 2016-2017.

Enclosed Documents

The existing library floor plan with the proposed library expansion footprint was included in the packet.

Presenters

Representatives from Broaddus & Associates attended the Facilities Committee meeting to present and respond to questions.

Upon a motion by Mr. Paul R. Rodriguez and a second by Ms. Rose Benavidez, the Facilities Committee recommended Board approval for staff to investigate the cost and options involved in incorporating the redesign and renovation of the existing library building with the 2013 Bond Construction Mid Valley Campus Library Expansion project as presented.

Review and Recommend Action on Contracting Mechanical, Electrical, Plumbing (MEP) Engineering Services for the Nursing and Allied Health Campus Thermal Plant

Approval to contract mechanical, engineering, and plumbing (MEP) engineering services to prepare plans for the Nursing & Allied Health Campus Thermal Plant project was scheduled to be requested at the September 22, 2015 Board meeting.

It was noted that the second-firm vendor scored more highly than the first-ranked firm in every area other than references, AND the second-ranked firm scored a 90 / 100 in the reference section, whereas the first-ranked firm scored a 99 / 100. Because of the disparity of scores depending on the inclusion or exclusion of references, and the method by which references were scored and weighted, the Facilities Committee took no action.

As part of the evaluation of responses the evaluation committee called references provided by each firm. In some cases, three or four of the five submitted references were contacted. In other cases, only two references could be reached for a response. Furthermore, all responses received were provided as numerical scores by the references. The evaluation committee used these scores in the ranking of firms. The Facilities Committee expressed concern with the process for evaluating firms' references.

Due these concerns over the criteria evaluation process, the Committee took no action and instructed staff to revise the process and re-evaluate the original responses. The evaluation committee was instructed to contact an equitable number of references for each firm, and then distribute the responses to the evaluation committee members, who could then consider the responses and individually score them.

The Facilities Committee took no action.

Review and Recommend Action on Substantial Completion for the Following Non-Bond Construction Projects

Approval of substantial completion for the following projects will be requested at the September 22, 2015 Board meeting:

	Projects	Substantial Completion	Final Completion	Documents Attached
1.	•	Recommended	Expected	Substantial Completion
	Drive and Sidewalk		October 2015	Certificate
	Engineer: R. Gutierrez			
	Engineering			
	Contractor: Roth Excavating			
2.	Pecan Campus Art Building	Recommended	Expected	Substantial Completion
	Existing Ceramic Arts Interior		October 2015	Certificate
	Renovations			
	Architect: EGV Architects			
	Contractor: Herrcon, LLC			
3.	•	Recommended	Expected	Substantial Completion
	Lighting Upgrades		October 2015	Certificate
	Engineer: DBR Engineering			
	Contractor: Metro Electric			

1. Pecan Campus AECHS Service Drive and Sidewalk

It was recommended that substantial completion for this project with Roth Excavating be approved.

R. Gutierrez and STC staff visited the site and developed a construction punch list. As a result of this site visit and observation of the completed work, a Certificate of Substantial Completion for the project was certified on August 14, 2015. Substantial Completion was accomplished within the time allowed in the Owner/Contractor agreement for this project. A copy of the Substantial Completion Certificate was included in the packet.

Contractor Roth Excavating would continue working on the punch list items identified and would have thirty (30) days to complete before final completion can be recommended for approval. It was anticipated that final acceptance of this project would be recommended for approval at the October 2015 Board meeting.

2. Pecan Campus Art Building Existing Ceramic Arts Interior Renovations

It was recommended that substantial completion for this project with Herrcon, LLC be approved.

Minutes September 10, 2015 Page 9, 9/17/2015 @ 11:51 AM

EGV Architects and STC staff visited the site and developed a construction punch list. As a result of this site visit and observation of the completed work, a Certificate of Substantial Completion for the project was certified on August 19, 2015. Substantial Completion was accomplished within the time allowed in the Owner/Contractor agreement for this project. A copy of the Substantial Completion Certificate was included in the packet.

Contractor Herrcon, LLC would continue working on the punch list items identified and would have thirty (30) days to complete before final completion can be recommended for approval. It was anticipated that final acceptance of this project would be recommended for approval at the October 2015 Board meeting.

3. District Wide Parking Lot Lighting Upgrades

It was recommended that substantial completion for this project with Metro Electric be approved.

DBR Engineering and STC staff visited the site and developed a construction punch list. As a result of this site visit and observation of the completed work, a Certificate of Substantial Completion for the project was certified on August 27, 2015. Substantial Completion was accomplished within the time allowed in the Owner/Contractor agreement for this project. A copy of the Substantial Completion Certificate was included in the packet.

Contractor Metro Electric would continue working on the punch list items identified and would have thirty (30) days to complete before final completion can be recommended for approval. It was anticipated that final acceptance of this project would be recommended for approval at the October 2015 Board meeting.

Upon a motion by Mr. Gary Gurwitz and a second by Mr. Paul R. Rodriguez, the Facilities Committee recommended Board approval of the substantial completion of the projects as presented. The motion carried.

Executive Session:

The South Texas College Board Facilities Committee convened into Executive Session at 5:03 p.m. in accordance with Chapter 551 of the Texas Government Code for the specific purpose provided in:

- Section 551.071, Consultations with Attorney
 - 1. Update on Status of Non-Bond Construction Projects

Open Session:

The South Texas College Board Facilities Committee returned to Open Session at 5:15 p.m. No action was taken in Executive Session.

Update on Status of Non-Bond Construction Projects

The Facilities Planning & Construction staff provided a design and construction update. This update summarized the status of each capital improvement project currently in progress. Mary Elizondo and Rick de la Garza attended the meeting to respond to questions and address concerns of the committee.

Staff was reviewing the following concern with the design team and contractor. They were not ready to recommend action by the Facilities Committee or Board at this time, and anticipated making an appropriate recommendation at a subsequent Facilities Committee meeting should it be necessary.

Upon a motion by Mr. Gary Gurwitz and a second by Ms. Rose Benavidez, the Facilities Committee recommended Board authorization for staff to address the final completion and close out of the Technology Campus Cooling Tower Replacement project as discussed in executive session. The motion carried.

Adjournment

There being no further business to discuss, the Facilities Committee Meeting of the South Texas College Board of Trustees adjourned at 5:16 p.m.

I certify that the foregoing are the true and correct minutes of the September 10, 2015 Facilities Committee Meeting of the South Texas College Board of Trustees.

Mr.	Gary	Gurwitz,	Chair	

Motions October 6, 2015 Page 3, 10/2/2015 @ 9:04 AM

Update on Status of 2013 Bond Construction Program

Enclosed is a copy of the presentation prepared by Broaddus & Associates as an update on the status of the 2013 Bond Construction Program. A representative from Broaddus & Associates will be present at the October 6, 2015 Board Facilities Committee meeting to provide the update.

	2013 BOND CONSTRUCTION PROGRAM PROGRESS REPORT - October 6, 2015	D CON	STRU	JCTIC	N P	ROGI	SAM F	ROG	RESS	REP	ORT	0.	tobe	6, 2	015		
					H		i	H	Price	H	,				H		
		Project	Project Development	obmen		Desig	Design Phase		Proposals	S	S S	struct	Construction Phase	ase		Architect/Engineer	Contractor
Project Number	PROJECT DESCRIPTION	Project Development Board approval of A/E	Contract Negotiations	Concept Development	Schematic Approval	%09 %0E	%96	%00L	wəivəЯ A&8	Board Approval	90% 30%	%9 <i>L</i>	95% Substantial Comp	%00L	Final Completion		
	Pecan Campus																
	North Academic Building														PBI	PBK Architects	D. Wilson Construction
	South Academic Building					Н		Н	Н	\vdash	\vdash			H	BS,	BSA Architects	D. Wilson Construction
	STEM Building					Н		H	Н						BS,	BSA Architects	D. Wilson Construction
	Student Activities Building and Cafeteria													H	Wa	Warren Group Architects	D. Wilson Construction
	Thermal Plant Expansion													H	Hal	Halff Associates	D. Wilson Construction
	Parking and Site Improvements					\dashv		\vdash	$\vdash \vdash$	\vdash	\vdash			\vdash	PCE	Щ.	D. Wilson Construction
	Mid Valley Campus										-			-	_		
	Health Professions and Science Building														ROI	ROFA Architects	Skanska USA
	Workforce Training Center Expansion														EG	EGV Architects	Skanska USA
	Library Expansion														Mat	Mata + Garcia Architects	Skanska USA
	Student Services Building Expansion							$\frac{1}{1}$	$\frac{1}{1}$						RO	ROFA Architects	Skanska USA
	Thermal Plant														DBF	DBR Engineering	Skanska USA
	Parking and Site Improvements					-		1	\dashv						Half	Halff Associates	Skanska USA
	Technology Campus																
	Southwest Building Renovation														EG	EGV Architects	ECON Construction
	Parking and Site Improvements														Ē	Hinojosa Engineering	ECON Construction
	Nursing and Allied Health Campus								-	1			-	-	_		
	Campus Expansion								H						ER	ERO Architects	D. Wilson Construction
	Parking and Site Improvements														<u>ж</u>	R. Gutierrez Engineers	D. Wilson Construction
	Starr County Campus									-	-				-		
	Health Professions and Science Building														Mat	Mata + Garcia Architects	D. Wilson Construction
	Workforce Training Center Expansion														EG	EGV Architects	D. Wilson Construction
	Library				\dashv	_		$\frac{1}{1}$	$\frac{1}{1}$						Mat	Mata + Garcia Architects	D. Wilson Construction
	Student Services Building Expansion														Mat	Mata + Garcia Architects	D. Wilson Construction
	Student Activities Building Expansion														Mat	Mata + Garcia Architects	D. Wilson Construction
	Thermal Plant														Sign	Sigma HN Engineers	D. Wilson Construction
	Parking and Site Improvements														Mel	Melden & Hunt Engineering	D. Wilson Construction
	Regional Center for Public Safety Excellence - Pharr	ence - P	harr								-						
	Training Facility														TBD	D	TBD
	Parking and Site Improvements				\dashv										TBD	Q	TBD
	STC La Joya Teaching Site (Jimmy Carter ECHS	ı ECHS	()										•				
	Training Labs Improvements				\dashv	\dashv	寸	\dashv	\dashv	\dashv	_			_	EG	EGV Architects	TBD
			1	1	l			-	-				1				

SOUTH TEXAS COLLEGE

2013 BOND CONSTRUCTION PROGRAM UPCOMING TIMELINE

Facilities Committee Meeting October 6, 2015



BOARD APPROVAL ITEMS

South Texas College 2013 Bond Construction Program Upcoming Timeline – 09/10/15

July '15 September '15 October '15

November '15

Update (No Action) Schematic Design Approval Nursing & Allied Health Thermal Energy Engineer Selection Chiller Procurement Additional Services MVC Library	Kenovation
	New Year
Update (No Action) Schematic Design Approval	
Update (No Action) Schematic Design Approval Approval Pecan Campus Thermal Energy Plant – Partial GMP	
Update (No Action) Schematic Design Approval	
1 2 & 4	6 8 9

OPERATIONAL ITEMS

South Texas College 2013 Bond Construction Program Upcoming Timeline

November '15 Procurement October '15 Chiller September '15 Update Master Plan Library Consultant Kitchen Consultant **BIM FM Execution** Schematic Design Nursing & Allied Health Thermal Focus Groups **Energy Plant Deliverables** August '15 Ongoing Kickoff Design Program Schedule **Material Testing** Execute CM@R Geotechnical & Update Master Contracts Contracts **July '15** Execute 0 3 S ∞ Operational

INFORMATION & PRESENTATION

ITEMS

South Texas College 2013 Bond Construction Program Upcoming Timeline

November '15	
October '15	
September '15	
August '15	
July '15	

Wage Scale Determination	OCIP Presentation							
7	3	4	w	9	7	8	6	10
	7	3 8	2 E 4	2 6 4 3		3 5 6 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7	2 & 4 & 5 & 7 & 8	5 6 8 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9

ITEMS REQUIRING BOARD FEEDBACK

South Texas College 2013 Bond Construction Program Upcoming Timeline

15										
November '15										
October '15										
September '15										
August '15	nal Plant N&AH Thermal for N&AH Energy Plant - RFQ									
July '15	Thermal Plant Solution for N&AH									
	1	2	3	4	5	9	7	8	6	10
	3	qpsck	ed Fee	iso & gni riup	Кe	sw	əjI			

Review and Recommend Action on Vendor Reference Process for Request for Construction Proposals and Request for Qualifications

Review and action on the process to evaluate vendor references for Requests for Construction Proposals and Requests for Qualifications for architects and engineers will be requested at the October 27, 2015 Board meeting.

Purpose

To review the current vendor reference process and to propose an updated vendor reference process for Requests for Construction Proposals and Requests for Qualifications for architects and engineers.

The non-bond construction evaluation committee will consist of members from the following departments: Facilities Planning and Construction, Facilities Maintenance and Operations, Purchasing, and Project Architect or Engineer. The Bond construction evaluation committee will include the above members and representatives from the Construction Program Manager for the bond program, Broaddus and Associates.

The current process for the evaluation of construction vendor references:

#	Vendor Reference Process	Department
1	The request for proposal or qualification requires a	RFP/RFQ
	minimum of five (5) reference to be submitted	
2	The Purchasing Department contacts the references	Purchasing
	with a phone call and/or via email	
3	The references complete each question with a rating	Purchasing
	and are provided a comments section	
4	All responses are returned by the reference via fax or	Purchasing
	email	
5	Reference ratings are averaged from all references	Purchasing
	received for each firm to arrive at the reference score.	
6	The reference score is used as one of the evaluation	Committee
	criteria	

The current process is designed to have each reference indicate to South Texas College how well the company performed for them by providing a numerical score to that performance. This made the factor more objective by removing the wide disparity in the interpretation of comments by each evaluator.

Other community colleges were surveyed and it was found that the following methods are utilized to evaluate references: numerical score and comments, comments only, or references are requested but are not contacted.

The proposed evaluation process for vendor references is as follows:

#	Vendor Reference Process	Department
1	Request 5 minimum to 10 maximum references per construction proposal or request for qualifications	RFP/RFQ
2	Develop the vendor reference questions project specific (proposal or qualifications)	Purchasing Department/Planning and Construction
3	Purchasing Department will contact the references and document responses	Purchasing Department
4	A minimum of four (4) responses will be collected from the vendor references.	Purchasing Department
5	All comments received from all references will be shared with the proposal or qualification evaluation committee for evaluation purposes.	Purchasing Department and Evaluation Committee
6	The evaluation committee members will review the comments provided by each reference and each evaluator will interpret the comments according to his/her own discretion and evaluate accordingly.	Evaluation Committee

Justification and Benefit

This proposed process will allow each evaluator to review and interpret the comments to provide points for this part of the evaluation criteria.

It is requested that the Facilities Committee recommend for Board approval at the October 27, 2015 Board meeting, the process to evaluate vendor references for Request for Construction Proposals and Requests for Qualifications for architects and engineers as presented.

Review and Recommend Action on Solicitation of Request for Proposals (RFP) for Owner Procurement of Thermal Energy Plant Chillers for 2013 Bond Construction Projects

Approval to solicit for Request for Proposals (RFP) for Owner Procurement of Thermal Energy Plant Chillers for the 2013 Bond Construction program will be requested at the October 27, 2015 Board meeting.

Purpose

The design process is proceeding on all the Thermal Energy Plants for each respective campus with the exception of Nursing and Allied Health Campus which will commence once the Mechanical Electrical Plumbing (MEP) Engineering firm is selected as Engineer of Record. As part of design process, it is the intent of South Texas College Facilities Operations & Maintenance Department to standardize manufactured equipment which would allow for consistent operations and maintenance procedures.

Justification

In addition to the standardization of having one chiller manufacturer, the consolidation of all required chillers will provide South Texas College considerable savings as part of volume procurement. This procurement will allow the College to identify the best value respondent based on criteria established within the Request for Proposals. The selection will be based on: 1.) Cost, 2.) Energy Efficiency, 3.) Service Commitment, 4.) Delivery Capability, 5.) Warranty, 6.) Refrigerant Life Cycle, and 7.) References.

The selection committee will consist of STC staff, Broaddus & Associates representatives, and the three MEP Engineering firms assigned to each respective campus for the thermal energy plant designs.

Background

As previously authorized by the Board of Trustees, three MEP Engineers have been executing the design for Thermal Energy Plants for Pecan, Mid Valley, and Starr County Campuses. The intent is to standardize equipment for maintenance and at the same time provide value for procurement of this equipment. These procurement funds are part of the 2013 Bond Construction Program.

Enclosed Documents

A schedule of water cooled chillers for various campuses is enclosed for the committee's review.

Presenters

Representatives from Broaddus & Associates will be present at the Facilities Committee meeting to respond to questions.

It is requested that the Facilities Committee recommend for Board approval at the October 27, 2015 Board meeting, to solicit Request for Proposals (RFP) for Owner Procurement of Thermal Energy Plant Chillers for the 2013 Bond Construction program as presented.

	STC - MID VALLEY CAMPUS - WATER COOLED CHILLER SCHEDULE						
	MARK	CH-1	CH-2	CH-3	CH-4		
	COOLING CAPACITY (TONS)	600	600	600	600		
GENERAL	MAX RATED NPLV kW/ton	0.334	0.334	0.334	0.334		
GEN	VOLT/PHASE/CYCLES	480/3/60	480/3/60	480/3/60	480/3/60		
	MCA (AMPS)	460	460	460	460		
	MOCP (AMPS)	800	800	800	800		
N.	WATER FLOW (GPM)	854	854	854	854		
RATC	EWT (°F)	56	56	56	56		
EVAPORATOR	MIN TUBE THICKNESS (IN)	0.025	0.025	0.025	0.025		
Ш	LWT (°F)	42	42	42	42		
∝	WATER FLOW (GPM)	1405	1405	1405	1405		
CONDENSER	EWT (F)	85	85	85	85		
OND	MIN TUBE THICKNESS (IN)	0.028	0.028	0.028	0.028		
	LWT (F)	95	95	95	95		
SIS	MANUFACTURER	YORK	YORK	YORK	YORK		
BA	MODEL	YMC2	YMC2	YMC2	YMC2		
DESIGN BASIS	OPERATING WEIGHT (LBS)	26,745	26,745	26,745	26,745		
DE	NOTES:						

^{1.} PROVIDE UNIT MOUNTED AFD (VFD) WITH ACTIVE HARMONIC FILTERS PER IEEE 519.

^{2.} PROVIDE UNIT WITH DDC INTERFACE LON OR BACNET.

^{**} PRODUCT INFORMATION PROVIDED BY DBR ENGINEERING.

	STC - STARR COUNTY CAMPUS - WATER COOLED CHILLER SCHEDULE					
	MARK	CH-1	CH-2	CH-3		
	COOLING CAPACITY (TONS)	500	500	500		
₹	MAX RATED NPLV kW/ton	0.327	0.327	0.327		
GENERAL	VOLT/PHASE/CYCLES	460/3/60	460/3/60	460/3/60		
ß	REFRIGERANT	R-134A	R-134A	R-134A		
	MCA (AMPS)	489	489	489		
	MOCP (AMPS)	683	683	683		
TOR	WATER FLOW (GPM)	1000	1000	1000		
EVAPORATOR	EWT (F)	43	43	43		
EVA	LWT (F)	55	55	55		
SER	WATER FLOW (GPM)	1500	1500	1500		
CONDENSER	EWT (F)	85	85	85		
CO	LWT (F)	95	95	95		
Sis	MANUFACTURER	DAIKIN	DAIKIN	DAIKIN		
d BAS	MODEL	WME-500	WME-500	WME-500		
DESIGN BASIS	OPERATING WEIGHT (LBS)	16,928	16,928	16,928		

NOTES:

- 1. PROVIDE SINGLE POINT POWER WITH NON-FUSED DISCONNECT
- 2. ALL CHILLERS TO BE PROVIDED WITH 3/4" THERMAL INSULATION ON COLD SURFACES
- 3. PROVIDE WITH BACKNET IP WITH ETHERNET COMMUNICATION CARD.
- 4. PROVIDE CHILLERS WITH FACTORY VFD'S.
- 5. PROVIDE FACTORY RUN TEST, FACTORY START-UP AND 5 YR WARRANTY ENTIRE UNIT PARTS, LABOR AND REPLACEMENT REFRIGERANT WARRANTY. START-UP AND WARRANTY TO BE EXECUTED BY A FACTORY SERVICE EMPLOYEE, NOT AN "AUTHORIZED AGENT/REPRESENTATIVE."
- 6. PROVIDE THERMAL DISPERSION TYPE WATER FLOW INDICATORS
- 7. PROIVDE .028" COPPER TUBES IN EVAPORATOR AND .035" COPPER TUBES IN CONDENSER
- 8. CHILLER SHALL UNLOAD TO 25% WITH 78F CONDENSER WATER
- ** PRODUCT INFORMATION PROVIDED BY SIGMA ENGINEERING.

	STC - PECAN CAMPUS - WA	TER COOLED CHILLE	R SCHEDULE	
	MARK	CH-4	CH-5	
	COOLING CAPACITY (TONS)	940	940	
ζΑ L	MAX RATED NPLV kW/ton	0.533	0.533	
GENERAL	VOLT/PHASE/CYCLES	460/3/60	460/3/60	
GE	REFRIGERANT	R-134a	R-134A	
	MCA (AMPS)	913	913	
	MOCP (AMPS)	1600	1600	
ATOR	WATER FLOW (GPM)	1880	1880	
EVAPORATOR	EWT (F)	55	55	
EVA	LWT (F)	43	43	
ISER	WATER FLOW (GPM)	2820	2820	
CONDENSER	EWT (F)	85	85	
00	LWT (F)	94.2	94.2	
Sis	MANUFACTURER	YORK	YORK	
N BA	MODEL	YK	YK	
DESIGN BASIS	OPERATING WEIGHT (LBS)	16,928	16,928	

NOTES:

- 1. ALL CHILLERS TO BE PROVIDED WITH 3/4" THERMAL INSULATION ON COLD SURFACES.
- 2. PROVIDE THERMAL DISPERSION TYPE WATER FLOW INDICATORS.
- 3. PROVIDE WITH BACNET IP WITH ETHERNET COMMUNICATION CARD.
- 4. PROVIDE .028" COPPER TUBES IN EVAPORATORS AND .035" COPPER TUBES IN CONDENSER.
- 5. PROVIDE CHILLERS WITH FACTORY VFD.
- 6. PROVIDE SINGLE POINT POWER WITH NON-FUSED DISCONNECT.]
- 7. CHILLER SHALL UNLOAD TO 25% WITH CONSTANT 85F CONDENSER WATER.

^{**} PRODUCT INFORMATION PROVIDED BY HALFF ASSOCIATES.

	STC - NURSING ALLIED H	EALTH SERVICES - WATER COO	LED CHILLER SCHEDULE			
	MARK	CH-1	CH-2			
	COOLING CAPACITY (TONS)	500	500			
ΑŽ	MAX RATED NPLV kW/ton					
GENERAL	VOLT/PHASE/CYCLES					
Э	REFRIGERANT	INFORMATION NOT YET ESTABLISHED				
	MCA (AMPS)					
	MOCP (AMPS)					
EVAPORATOR	WATER FLOW (GPM)					
POR/	EWT (F)	INFORMATION NOT YET ESTABLISHED				
EVAI	LWT (F)					
SER	WATER FLOW (GPM)					
CONDENSER	EWT (F)	INFORMATION NOT	YET ESTABLISHED			
00	LWT (F)					
Sis	MANUFACTURER	YORK	YORK			
Z BAS	MODEL					
DESIGN BASIS	OPERATING WEIGHT (LBS)					
Ω						

NOTES:

^{**}SUFFICIENT INFORMATION HAS NOT YET BEEN ESTABLISHED FOR THIS PARTICULAR PROJECT SINCE A DESIGN TEAM HAS NOT BEEN OFFICIALLY AWARDED THIS PROJECT.

Review and Recommend Action on Contracting Mechanical, Electrical, Plumbing (MEP) Engineering Services for the Nursing and Allied Health Campus Thermal Plant

Approval to contract mechanical, engineering, and plumbing (MEP) engineering services to prepare plans for the Nursing & Allied Health Campus Thermal Plant project will be requested at the October 27, 2015 Board meeting.

Purpose

Mechanical, Electrical, Plumbing (MEP) professional engineering services are necessary for design and construction administration services for the thermal energy plant project. The engineering scope of work includes, but is not limited to, design, analysis, preparation of plans and specifications, permit applications, construction administration, and inspection for the thermal plant.

Justification

This thermal energy plant project will provide heating, ventilation, and air conditioning (HVAC) systems for the existing facilities located on the South Texas College Nursing & Allied Health Campus as well as for the new 2013 Bond Construction Nursing & Allied Health Campus expansion project.

The current HVAC systems in the existing buildings are air cooled chiller systems and are near their "end of useful life" periods and scheduled to be replaced. The proposed thermal plant will be designed as a water cooled chiller system servicing all three buildings.

The 2013 Bond Nursing & Allied Health Campus Expansion project budget will include:

- HVAC system within the building
- Chilled water piping extending to the new proposed thermal plant

The proposed Nursing & Allied Health Thermal Plant project budget will include:

- New thermal plant facility
- New water cooled chillers
- New cooling towers
- New piping to the existing buildings
- Retrofitting of the existing system to accept the new thermal plant system
- Removal and salvaging of existing air cooled chillers

Background

On August 3, 2015, STC began soliciting MEP engineering qualifications for the purpose of selecting a firm to prepare the necessary plans for the thermal plant. A total of eight (8) firms received a copy of the RFQ and a total of five (5) firms submitted their responses on August 19, 2015.

On September 10th, 2015, the Facilities Committee recommended a vendor reference process which staff has followed and completed. The evaluation committee has evaluated

Motions October 6, 2015 Page 11, 10/2/2015 @ 9:04 AM

a minimum of four references as directed by the Facilities Committee. The comments received from each reference were provided to the evaluation committee and evaluated by each member of the evaluation committee.


Funding Source

Funds for these expenditures are budgeted in the non-bond construction budget for FY 2015-2016.

Enclosed Documents

A site plan indicating the location of the proposed thermal plant is enclosed. STC staff members completed evaluations for the firms and prepared the enclosed scoring and ranking summary. A blank evaluation form and a blank vendor reference from are also enclosed for the committee's review.

It is requested that the Facilities Committee recommend for Board approval at the October 27, 2015 Board meeting, the contracting of mechanical, engineering, and plumbing (MEP) engineering services with Halff Associates for preparation of plans for the Nursing & Allied Health Campus Thermal Plant project as presented.



SOUTH TEXAS COLLEGE MECHANICAL, ELECTRICAL, AND PLUMBING ENGINEERING SERVICES PROJECT NO. 15-16-1015

VENDOD	DBR	Ethos	Halff	MEP Solutions	Sigma HN
VENDOR ADDRESS	Engineering Consultants, Inc. 200 S 10th St Ste 901	Engineering 119 W Van Buren Ave Ste 101	Associates, Inc. 5000 W Military Ste 100	Engineering, PLLC. 600 E Beaumont Ave Ste 2	Engineers, PLLC. 701 S 15th St
CITY/STATE/ZIP	McAllen, TX 78501	Harlingen, TX 78550	McAllen, TX 78503	McAllen, TX 78501	McAllen, TX 78501
PHONE FAX	956-683-1640 956-683-1903	956-230-3435 956-720-0830	956-664-0286 956-664-0282	956-664-2727 956-664-2726	956-332-3206 956-687-5561
CONTACT	Edward Puentes	Cesar Gonzalez	Menton Murray III	Luis Javier Pena	Jesus Gabriel Hinojosa
3.1 Statement of Interest 3.1.1 Statement of Interest on projects	for STC recently, including services for a thermal plant at Mid-Valley Campus. Indicated their understanding of STC's	Pointed out the personnel's experience in providing services. Emphasized their previous work for STC and therefore their familiarity with the campuses, staff and design standards.	Pointed to the firm's work already provided to the college in the past. Added that they have first-hand knowledge of the NAH Campus from the previous projects and the design of MEP systems for the new building at the campus under the 2013 Bond Program.	municipalities, universities, healthcare and	The firm emphasized the experience of the two principals within the firm. They indicated that STC would be working directly with the two principals and pointed out that the firm's size would be better able to meet the needs in a cost-effective manner.
3.1.2 Firm History and Credentials	- Providing services since 1972 - 117 staff member in 5 offices in Texas - 22 licensed engineers - 14 LEED accredited professionals	- 8 full time employees - 2 registered engineers - Firm established in spring of 2014	- Founded in Dallas in 1950 - Has 13 offices in Texas - McAllen office since 1994 - About 550 total staff	engineers	Established in 2012. Indicated a combined 15 years experience of the two principals. Stated that they have completed over 100 projects with 20 of these for higher education.
3.1.3 Narrative describing firm's qualifications and specialized design experience	plants for educational clients and their current work for STC on a thermal plant	Summarized the experience of the three top staff members (20, 25 and 9 years). Emphasized the experience of one of their principals in the design of large central plants and thermal energy storage projects.	Firm stated their familiarity with the existing STC HVAC systems and their distribution systems and in particular, their design of the system at the Pecan and Starr County campuses.		Pointed out the work of the two principals on thermal energy projects for STC and various school districts.
3.1.4 Statement of Availability and Commitment of firm, consultants, and key professionals	Indicated that staff are qualified and prepared to dedicate themselves to the project. Pointed to the availability of staff from other offices to assist if needed.	Indicated that they are available as soon as they are awarded and will make the STC project their top priority.	Indicated that the staff identified will be ready and available for the project. They pointed to the depth of staff at their McAllen office and the support from other offices.	Firm did not directly address this section of the RFQ, but had indicated that the project manager will dedicate the required time to scheduled milestones.	Indicated that firm has the resources and is prepared to perform work for STC. Listed a staff of seven, including the principals. Stated that they will ensure the necessary resources for the project.
3.2 Prime Firm				Provided resumes for the two professional	
expertise of principles and key members, Including resumes	Included resumes for the following staff: - Edward Puentes, PE, Partner in Charge/Project Manager - Antonio Salazar, Jr., Mechanical Designer - Thomas Raveney, EIT, Electrical Designer - Maritza Garza, EIT, Plumbing Designer	Included resumes for the following staff: - Rajesh Kapileshwari, PE, Principal - Guillermo Quintanilla, Principal - Cesar Gonzalez, PE, Principal	- Menton "Trey" Murray III, PE, Project Leader - Robert Tijerina, EIT, HVAC/Plumbing - Hugo H. Avila, PE, HVAC/Plumbing - Tom Dearmin, PE, LEED AP, Electrical - Robert L. Saenz, PE, CFM, Civil Principal - Benjamin E. Macias, PE, Civil Project Manager - Raul Garcia Jr., PE CFM, Drainage/Site Design	engineers: - Luis Javier Pena, PE - Abram L. Dominguez, PE	- Jesus Gabriel Hinojosa, PE, LEED AP - Jose Antonio Nicanor, PE, LEED AP
3.2.2 Proposed project assignments, lines of authority, estimated time assignment of personnel	each will devote to the project.	Indicated the specific duties of all three principals and other staff who will be involved in project. Indicated that the principals will devote from 66% to 100% of their time to the project. Lines of authority are shown in the organization chart submitted.	Showed time assignments for the four top staff member from firm who will be involved in the project. Also included the time assignment by the architect for the project and the Structural design subconsultant.	submitted, but is shown on the organization chart.	Indicated a 100% time commitment from both principles for the project and provided the time commitments from the five other staff.
3.2.3 Prime Firm's Proximity to College and ability to respond to project needs	Pointed to their McAllen location and that they are only 10 minutes away from the STC Nursing & Allied Health Campus.	Located in Harlingen. Indicate that they are able to respond to calls for meetings in about an hour.	Located in McAllen. Stated that they are 10 minutes away from the STC Nursing and Allied Health Campus.	close proximity to STC.	Location is in McAllen. Indicated that their office is 2.5 miles from the campus and this means they are five minutes away.
3.2.4. Prime Firm's experience with Building Information Model		Stated that firm staff has used BIM models for several years. They added that the firm has the software and design expertise to design the project in an integrated BIM environment.	Indicated that the McAllen team has used BIM on more than 25 projects in the last 5 years. Has designed three water-cooled plants using BIM.	2011.	Indicated that the two principals underwent training on Revit in 2011. Currently using BIM software for Starr County Campus thermal plant project and have used on other projects.
3.2.5 Litigation prime firm is involved in	Indicated that there is no past or pending litigation that would affect ability to provide services to STC.		Stated that because of the size and the number of projects the firm is involved in, it is occasionally a defendant in litigation, but indicated that there are no present matters that would affect the firm's ability to meet obligations on the project.	litigation.	Indicated that they are not currently involved in litigation that would affect ability to provide services to STC.
3.3 Project Team					
3.3.1 Organization chart with Role of Prime Firm and basic Services consultants	who will be assigned to project and also	Included organization chart that showed all firm staff and which included the following subconsultants: - Boultinghouse Simpson Gates Architects - Architect - Green Rubiano & Associates - Structural Engineer - Perez Consulting Engineers - Civil Engineer	-ERO Architects - Architectural	9	Organization chart was included showing the primary role of the two principals and which included two subconsultants. The subconsultants are: - Mata Garcia Architects - CLH Engineering
3.4 Representative Projects	3				

SOUTH TEXAS COLLEGE MECHANICAL, ELECTRICAL, AND PLUMBING ENGINEERING SERVICES PROJECT NO. 15-16-1015

	DBR	Ethos	Halff	MEP Solutions	Sigma HN
VENDOR	Engineering Consultants, Inc.	Engineering	Associates, Inc.	Engineering, PLLC.	Engineers, PLLC.
3.4.1 Minimum of 5 projects firm has worked on	- South Texas College - Mid Valley Campus - Central Thermal Plant (\$3.8 million) - Klein ISD - Klein High School (\$103,548,388) - Rio Grande City CISD - Rio Grande City High School (\$52,268,703) - Blinn College - Chiller Replacement and Central Plant Upgrade (\$585,515)	- South Texas ISD - BETA Campus Chiller Replacements (\$1,612,744) - Brownsville ISD - Veterans Memorial High School (\$60,000,000) - Los Fresnos CISD - Los Fresnos United 9th Grade Center (\$50,000) - Valley International Airport - Mechanical Upgrades (\$2,163,395) - Idea Academy - Headquarters Building (\$11,500,000)	-	- Donna ISD - Donna North High School (\$46,500,000) - PSJA ISD - T-STEM Early College High School - Phase I Renovations and Additions (\$8,087,000) - PSJA ISD - T-STEM Early College High School - Phase II (\$9,691,000) - PSJA ISD - Science Lab Classroom Additions (\$7,478,000) - IDEA Academy, (three locations for total of \$12,388,080)	- La Joya ISD - Hidalgo County FEMA Safe Room (\$5.75 million) - STC - Pecan Campus Student Services Building Modifications (\$350,000) - UT-Pan American - NECC/MAGC Chilled Water Piping (\$200,000) - Edinburg CISD - Freddy Gonzalez Elementary School Renovations (\$1.36 million) - South Texas College Starr County Thermal Plant Expansion (\$3.8 million)
3.5 References					
3.5.1 References	- Texas State Technical College - UT-Pan American - Texas Southmost College - La Joya ISD - Blinn College - Edinburg CISD - PSJA ISD - City of McAllen - McAllen ISD - Harlingen ISD	- South Texas ISD - Brownsville ISD - Los Fresnos CISD - Valley International Airport - Idea Public Schools	- Texas State Technical College - UT-Pan American - McAllen ISD - La Joya ISD - Mission CISD	Boultinghouse Simpson Gates Architects ERO Architects ROFA Architects PBK Architects The Warran Group Architects	- La Joya ISD - UT-RGV - UT- Pan American - Hidalgo County, Precinct 4 - Edinburg CISD - Donna ISD
3.6 Project Execution					
3.6.1 Willingness and ability to expedite services. Ability to supplement production.	Indicated their ability to expedite design services. Reiterated the availability of staff from other office within Texas.	Reiterated their commitment to the project, including commitment by their subconsultants. Stated that they are willing to add more design staff if needed.	Indicated that their staff of 20 at the McAllen office provides a production capacity that no other local firm can match. Also added that staff from other offices are available if needed.	Stated their willingness to expedite design services and construction administration for the project.	Indicated that meeting schedules and accelerated timelines is part of the firm's culture. Stated that they are willing and able to expedite services. Pointed to a proven track record for the two principals.
Total Evaluation Points	550.73	559.81	566.72	504.15	540.97
Ranking	3	2	1	5	4

SOUTH TEXAS COLLEGE MECHANICAL, ELECTRICAL, AND PLUMBING ENGINEERING SERVICES PROJECT NO. 15-16-1015 EVALUATION SUMMARY

	NAME	DBR Eng Consulta		Eth Engine		Ha Associat		MEP So Engineerir		Sigm. Engineer		
	ADDRESS	200 S 10th	St Ste 901	119 W Van Ste		5000 W Ste	,	600 E Beau Ste		701 S 1	15th St	
CITY/STATE/ZIP		McAllen, TX 78501		Harlingen, TX 78550		McAllen, TX 78503		McAllen, TX 78501		McAllen, TX 78501		
PHONE		956-683-1640		956-230-3435		956-664-0286		956-664-2727		956-332-3206		
	FAX	956-683	956-683-1903		956-720-0830		956-664-0282		956-664-2726		956-687-5561	
	CONTACT	Edward I		Cesar G	onzalez	Menton N		Luis Javi	er Pena	Jesus Gabriel Hinojosa		
		86		93		92	j	84		85		
	3.1 Statement of Interest - up to 100 points	95		97	1	98		90		94	-	
	3.1.1 Statement of interest on projects 3.1.2 Firm History and Credentials	90		85	1	95		70		85		
1	3.1.3 Narrative describing firm's qualification and specialized design experience	91	91.5	97	93.5	95	95	80	84.5	85	89	
	3.1.4 Availability and commitment of firm, consultants and key professionals	92	1	95]	95		90		92	-	
		95		94	1	95		93		93	-	
	3.2 Prime Firm - up to 100 points	85		92		90		76		89		
	3.2.1 Experience and expertise of principles and key members, including resumes	93		95	1	95	1	85		89		
	3.2.2 Proposed project assignments, lines of authority, estimated time assignment of personnel	95	04.44	85		95	0.4.47	65	00	80	89.66	
2	3.2.3 Firm's proximity to college and ability to respond to project needs	93	91.66	98	92.83	95	94.16	95	83	97		
	3.4.2 Firm's experience with Building Information	90		93		95	1	85		90		
	Modeling 3.2.5 Litigation prime firm is involved in	94		94	1	95	1	92	_	93		
	3.3 Project Team - up to 100 points	90		92		94		80		89		
	3.3.1 Organizational chart showing, the roles of the prime firm and basic services consultants	95		95		90	94.16	60	71 14	89	1	
	Name Consultant and provide brief historyConsultant's proposed role in project	95	00.5	85	00.17	95		65		80	89.33	
3	Projects Consultant and prime have worked together on in last 5 years	95	93.5	99	93.16	96		50	71.16	93		
	Statement of Consultant's availability for this project	92		95		95		80	┥	92		
	Resumes showing experience and expertise of key individuals	94		93		95		92		93		
	3.4 Representative Projects - up to 100 points	86		90		92		80		84		
	3.4.1 Specific data on 5 representative projects Project name and location, Project owner and contact	90		93		95	95.16	85	1	89	1	
4	information, project construction cost, project size in	90	90.66	85	92.16	95		75	84.33	85	89.16	
4	gross square feet, date project was stated and completed, professional services prime firm provided	95	70.00	97	92.10	99	95.10	85	04.33	93	09.10	
	for the project, project manager, project engineer, project designer, names of consultant firms and their	90		95		95		90		93		
	expertise and description of BIM processes.	93		93		95		91		91		
		90		95		93.75		90		95]	
		92.5		95		93.75		95	92	95		
5	3.5 Five References - up to 100 points3.5.1 Name Owner and Owner's Representative	90	90.91	96	95.5	94	94.08	92		92	93.66	
	and phone numbers	90	70.71	99	70.0	95	71.00	95	72	95	70.00	
	and phone numbers	92		94		95		89		93		
		91		94		93		91		92		
		86		92]	92		80		84]	
		95		95	_	95		95		95]	
6	3.6 Project Execution - up to 100 points 3.6.1 Willingness and ability to expedite design	90	92.5	80	92.66	90	94.16	75	89.16	80	90.16	
	and construction administration for project.	97		99		98		98		95		
	, ,	92		95	_	95		92		92	<u> </u>	
·		95		95		95		95		95		
<u> </u>	TAL EVALUATION POINTS	550		559		566		504		540		
ΚA	NKING	3)	4	2	1		5	1	4	ł	

South Texas College Statement of Qualifications for Mechanical, Electrical and Plumbing Engineering Services RFQ Evaluations Project No.

Evaluator:							
	CRITERIA	Criteria Weight	Vendor	Vendor	Vendor	Vendor	Vendor
3.1 Statem	3.1 Statement of Interest	100					
3.1.1	Statement of interest on projects						
3.1.2	Firm History and credential						
3.1.3	Narrative describing firm's qualification and specialized design experience						
3.1.4	Availability and commitment of firm, consultants and key professionals						
3.2 Prime Firm	im.	100					
3.2.1	Experience and expertise of principles and key members, Including resumes						
3.2.2	Proposed project assignments, lines of authority, estimated time assignment of personnel						
3.2.3	Firm's proximity to college and ability to respond to project needs						
3.2.4	Firm's experience with Building Information Modeling						
3.2.5	Litigation prime firm is involved in						
3.3 Project Team	Team	100					
3.3.1	Organizational chart showing, the roles of the prime firm and basic services consultants						
	Name Consultant and provide brief history						
	Consultant's proposed role in project						
	Projects Consultant and prime have worked together on in last 5 year						
	Statement of Consultant's availability for this project						
	Resumes showing experience and expertise of key individuals						
3.4 Repres	3.4 Representative Projects	100					
3.4.1	Specific data on 5 representative projects						
	Project name and location						
	Project Owner and contact information						
	Project construction cost						
	Project size in gross square feet						
	Date project was started and completed						
	Professional services prime firm provided for the project						
	Project manager						
	Project engineer						
	Project designer						
	Names of consultant firms and their expertise.						
	Description of BIM processes						
3.5 Five References	ferences	100					
3.5.1	Name Owner and Owner's Representative and phone numbers.						
3.6 Project Execution	Execution	100					
3.6.1	Willingness and abilty to expedite design and construction administration for project.						
TOTAL:		009	0	0	0	0	0

Reference Questionnaire

Refere	nce for (firm name):
Person	called:
We red	quest your responses to the below questions. Please provide comments.
1.	How do you rate the quality of the firm's work?
	Comments:
2.	Do they have knowledgeable and qualified staff? Please explain.
	Comments:
3.	How responsive was the firm in addressing any concerns or issues that came up?
	Comments:
4.	How well did the firm meet schedules?
	Comments:
5.	Did the firm staff communicate well with your staff? Please explain.
	Comments:
6.	How well did the firm fulfill contractual obligations from beginning to end of the project?
	Comments:
7.	Would you recommend them? Please explain.
	Comments:
г	
	For STC Use:
	Person conducting reference check:
	Date reference questionnaire was conducted or sent:

Review and Recommend Action to Incorporate the Redesign and Renovation of the Existing Library Building with the 2013 Bond Construction Mid Valley Campus Library Expansion Project

Approval to incorporate the redesign and renovation of the existing library building with the 2013 Bond Construction Mid Valley Campus Library Expansion project, will be requested at the October 27, 2015 Board meeting.

Purpose

Authorization is being requested to incorporate the redesign and renovation of the existing library building with the 2013 Bond Construction Mid Valley Campus Library Expansion project.

Justification

Incorporating the redesign and renovation of the existing library space with the design and construction of the 2013 Bond Construction Mid Valley Campus Library Expansion project will provide a comprehensive and functional design to meet present and future student needs. The design of the entire library space would allow for future planning, coordination of temporary library services, cost estimating, and scheduling for the construction of the existing library space.

Background

The 2013 Bond Construction Mid Valley Campus Library project is an expansion of the existing library facility. The planning process to incorporate both the renovation and the expansion projects began in 2012.

The existing library facility consists of 24,000 square feet and the proposed 2013 Bond Construction Library Expansion space consists of approximately 10,000 additional square feet. Please refer to Exhibit A – Existing Library Plan

Staff has gathered information regarding the integration of the two spaces to function as a cohesive whole, as stated below:

Library functions – Please refer to Exhibit B – Library Flow Diagram

- Changes in library functions and spaces
- Proliferation of mobile technology
- Changes in pedagogy
- Anticipated future enrollment growth

Space adjacencies – Please refer to Exhibit C – Space Adjacency Plan

- Preliminary discussion and development of adjacencies began in 2012
- Library staff gathered data reflecting the level of satisfaction with current library facilities from 2008 to present.
- This data is being utilized by the design team to plan and integrate the existing and proposed library spaces

 720 Design (library design consultant) was authorized by the STC Board on May 26, 2015 to develop the program and integrate an interior library design concept plan for the new library expansion, as well as, for the existing library building

Preliminary Anticipated Costs – Please refer to Exhibit D – Cost Summary

- Entire renovation project \$2,200,000
- Phased renovation project The overall cost will increase by an additional amount of \$63,210 for a total cost of \$2,263,210.

Budget Options – Possible options for consideration are:

- Non-bond construction budget
- Possible bond construction project savings

Library Service Continuity – Please refer to Exhibit E – Plan for Continuity for Library Services at Mid Valley Campus

- Anticipated limitation of library services for 6-8 months
- Plan has been developed including the relocation of the Library services to the Center for Learning Excellence Building and the distribution of Library books to other campuses

Current Architect

As previously authorized by the Board of Trustees, Mata Garcia Architects began
working with Broaddus & Associates, Facilities Planning & Construction, and STC
staff to develop the schematic design for the 2013 Bond Construction Mid Valley
Campus Library Expansion. On May 26, 2015, the Board approved additional
services to Mata Garcia Architect's contract, to allow 720 Design, Inc. to provide
an interior library design concept plan for the new library expansion as well as for
the existing library building.

Current Construction Manager-at-Risk

 At the April 28, 2015 Board meeting, the Board awarded the Construction Manager-at-Risk contract to Skanska Building USA to provide construction services for the 2013 Bond Construction Mid Valley Campus projects.

Anticipated Fees

- Architect fees: approximately 8.25% of construction cost, \$120,000 (negotiable)
- Program Manager fees: None anticipated due to costs being under the 5% threshold allowed in the contract
- Library consultant fees: Fees are included as part of previously approved additional services with Mata Garcia Architects
- Construction Manager-at-Risk: 3.6% of construction cost, \$52,200

Motions October 6, 2015 Page 15, 10/2/2015 @ 9:04 AM

Enclosed Documents

Exhibit A - Existing Library Plan, Exhibit B - Library Flow Diagram, Exhibit C - Space Adjacency Plan, Exhibit D - Cost Summary, Exhibit E - Plan for Continuity for Library Services at Mid Valley Campus

Presenters

Representatives from Broaddus & Associates will be present at the Facilities Committee meeting to respond to questions.

It is requested that the Facilities Committee recommend to incorporate the redesign and renovation of the existing library building with the 2013 Bond Construction Mid Valley Campus Library Expansion project at the October 27, 2015, Board meeting.

Exhibit A - Existing Library Plan





Exhibit B - Library Flow Diagram

11000 METATOR OF THE PERSON AND THE PERSON 411 120 120 9 3 NAME OF THE PERSON Quiet ¥ . Learning on Display 135 **Transition 1** 1 1 Sold Sold NO. P. Learning Shedy Shedy 2703 HATE A **Loud** 3/32"=1'-0" North Shady Shady Shady To Lay

Mid Valley Campus Library Concept:



Mid-Valley Campus Library Space Adjacency Plan



Exhibit C - Space Adjacency Plan

Exhibit D - Cost Summary

MVC Library Renovation Non-Bond Opinion of Probable Project Costs South Texas College

Construction Project Description	Square Feet	Construction Design	Design	FFE	Technology	Security	Technology Security Contingency	Miscellaneous	Program Management	Total Cost
				Mid I	Mid Valley Campus	sndı				
Renovation of Existing Library Space	15,555	1,450,000	119,600	425,000	75,000	20,000	72,500	2,000	0	2,164,100
Phase I	10,000	1,028,600	84,850	300,000	35,000	15,000	51,430	1,500		1,516,380
Phase II	3,000	176,000	14,520	35,000	20,000	0	8,800	1,500		255,820
Phase III	1,800	182,400	15,040	80,000	10,000	0	9,120	1,500		298,060
Alt. Art Gallery	755	63,000	5,190	10,000	10,000	5,000	3,150	1,500		97,840
Total	15,555	1,450,000	119,600	425,000	75,000	20,000	72,500	6,000	0	2,168,100
Additional										

Additional
construction costs
for project if
phased separately
such as
mobilization and
inflation

63,210.00

Exhibit E Plan for Continuity of Mid-Valley Library Services:

Anticipated Length of Service Limitation: 8-12 months

Library Staff:

• Library Staff will operate out of the CLE in Building A.

Library Collection

- A small collection of the most-circulated books will be housed in the CLE with the Library for quick access and checkout. Other books will be redistributed to other campuses or stored.
- Items from other campuses will be available through intra-campus loan with a turnaround time of one business day.

Study Space:

- The CLE has limited study rooms and study space for students to use during the closure of the library.
- Librarians and other staff will be available to assist students with searching for electronic resources and other library related questions.

Library Open Computers:

- The south end of the existing library, with the open computer labs, will remain open during the construction and initial renovations.
- Building G, Room 207, and Building A, Room 105, can be used for additional open computer lab space if needed.

Library Art Gallery

• The Library Art Gallery will be temporarily relocated to another location on campus, most likely the lobby of Building G.

Review and Recommend Action on Increased Design Services for Mata Garcia Architects to Incorporate the Redesign of the Existing Library Building with the 2013 Bond Construction Mid Valley Campus Library Expansion Project

Approval to increase design services with Mata Garcia Architects to incorporate the redesign of the existing library building with the 2013 Bond Construction Mid Valley Campus Library Expansion project, will be requested at the October 27, 2015 Board meeting.

Purpose

Authorization is being requested to increase design services for Mata Garcia Architects to incorporate the redesign of the existing library building with the 2013 Bond Construction Mid Valley Campus Library Expansion project.

Justification

Incorporating the redesign of the existing library space with the design of the 2013 Bond Construction Mid Valley Campus Library Expansion project will provide a comprehensive and functional design to meet student present and future needs. The schematic design of the entire library space would allow for future planning, coordination of temporary library services, cost estimating, and scheduling for the construction of the existing library space. The current architect authorized to design the 2013 Bond Construction Mid Valley Library Expansion is familiar with the conditions of the existing library and how the library should function with the design of the expansion.

Background

As previously authorized by the Board of Trustees, Mata Garcia Architects began working with Broaddus & Associates, Facilities Planning & Construction, and STC staff to develop the schematic design for the 2013 Bond Construction Mid Valley Campus Library Expansion. On May 26, 2015, the Board approved additional services to Mata Garcia Architect's contract, to allow 720 Design, Inc. to provide an interior library design concept plan for the new library expansion as well as for the existing library building.

Based on the current adjacency designs being developed by 720 Design, Inc., Broaddus & Associates, Facilities Planning & Construction, and STC library staff recognize the efficient value in incorporating the architectural services of the existing library space with the proposed expansion of the library by using the same architectural design team.

The proposed fees for Mata Garcia Architects to provide the increased design services are estimated to be approximately \$120,000. This fee may be adjusted based upon the estimated construction cost and negotiated percentage fee to perform the design services. Broaddus & Associates and STC staff will work with the architects to define the project scope and negotiate a percentage fee for the architectural services.

Presenters

Representatives from Broaddus & Associates will be present at the Facilities Committee meeting to respond to questions.

Motions October 6, 2015 Page 18, 10/2/2015 @ 9:04 AM

It is requested that the Facilities Committee recommend approval to increase design services with Mata Garcia Architects to incorporate the redesign of the existing library building with the 2013 Bond Construction Mid Valley Campus Library Expansion project at the October 27, 2015, Board meeting.

Review and Recommend Action on Schematic Design of the 2013 Bond Construction Mid Valley Campus Parking and Site Improvements

Approval of schematic design by Halff Associates for the 2013 Bond Construction Mid Valley Campus Parking and Site Improvements project will be requested at the October 27, 2015 Board meeting.

Purpose

Schematic design is the first phase of basic design services provided by the project design team. In this phase, the design team prepares schematic drawings based on the Owner's project program and design meetings with staff. The approval of this phase is necessary to establish the basis on which the project design team is given authorization to proceed with design development and construction document phases.

Justification

Once schematic design is approved, Halff Associates will proceed to prepare all necessary design development drawings and specifications in preparation for the construction documents phase using STC design standards as well as all applicable codes and ordinances. The phases of a construction project are as follows: 1.) Schematic Design, 2.) Design Development, 3.) Construction Documents, 4.) Guaranteed Maximum Price, 5.) Construction, and 6.) Closeout

The Construction Manager-at-Risk provides preconstruction services during the design processes leading to the construction phase. A Guaranteed Maximum Price (GMP) will then be developed and will be presented to the Facilities Committee for review at a future date.

Background

As previously authorized by the Board of Trustees, Halff Associates began working with Broaddus & Associates, Facilities Planning & Construction, and STC staff to develop parking and site plans. The proposed Mid Valley Campus Parking and Site Improvements project is part of the 2013 Bond Construction Program and includes the following scope:

- > Engineer
 - Halff Associates
- Construction Manager-at-Risk
 - Skanska USA Building
- Construction Cost Limitation (CCL)
 - \$2,000,000
- > Program Scope
 - 154 Parking Spaces
 - Drives and Sidewalks
 - Infrastructure Improvements

Motions October 6, 2015 Page 20, 10/2/2015 @ 9:04 AM

- Landscaping and Irrigation
- Grading

Funding Source

The current Construction Cost Limitation (CCL) is \$2,000,000 and will be adjusted once the Guaranteed Maximum Price (GMP) proposals have been submitted by the Construction Manager-at-Risk to be presented to the Board for approval. Bond funds are budgeted in the Bond Construction budget for fiscal year 2015-2016.

Reviewers

The proposed schematic design has been reviewed by Broaddus & Associates and staff from Facilities Planning & Construction, Operations and Maintenance, Administration, Technology Resources departments, and Campus Coordinator.


Enclosed Documents


Halff Associates has developed a schematic presentation describing the proposed design. Enclosed are drawings of the site plans.

Presenters

Halff Associates has developed a schematic presentation describing the proposed design. Representatives from Broaddus & Associates and Halff Associates will be present at the Facilities Committee meeting to present the schematic design of the proposed parking and site improvements.

It is requested that the Facilities Committee recommend for Board approval at the October 27, 2015 Board meeting, the proposed schematic design by Halff Associates for the 2013 Bond Construction Mid Valley Campus Parking and Site Improvements project as presented.





LEGEND

PROPOSED EXISTING































TREES

OVERALL SITE PLAN






SOUTH TEXAS COLLEGE MID VALLEY CAMPUS SITE IMPROVEMENTS














2 - BUILDING "D" ADDITION









3 - PROP. PARKING LOT










4 - BUILDING "E" ADDITION AND PROP. HEALTH PROFESSIONS & SCIENCE BUILDING







5 - BUILDING "F" ADDITION



Review and Recommend Action on Schematic Design of the 2013 Bond Construction Technology Campus Parking and Site Improvements

Approval of schematic design by Hinojosa Engineering for the 2013 Bond Construction Technology Campus Parking and Site Improvements project will be requested at the October 27, 2015 Board meeting.

Purpose

Schematic design is the first phase of basic design services provided by the project design team. In this phase, the design team prepares schematic drawings based on the Owner's project program and design meetings with staff. The approval of this phase is necessary to establish the basis on which the project design team is given authorization to proceed with design development and construction document phases.

Justification

Once schematic design is approved, Hinojosa Engineering will proceed to prepare all necessary design development drawings and specifications in preparation for the construction documents phase using STC design standards as well as all applicable codes and ordinances. The phases of a construction project are as follows: 1.) Schematic Design, 2.) Design Development, 3.) Construction Documents, 4.) Guaranteed Maximum Price, 5.) Construction, and 6.) Closeout

The Construction Manager-at-Risk provides preconstruction services during the design processes leading to the construction phase. A Guaranteed Maximum Price (GMP) will then be developed and will be presented to the Facilities Committee for review at a future date.

Background

As previously authorized by the Board of Trustees, Hinojosa Engineering began working with Broaddus & Associates, Facilities Planning & Construction, and STC staff to develop parking and site plans. The proposed Technology Campus Parking and Site Improvements project is part of the 2013 Bond Construction Program and includes the following scope:

- > Engineer
 - Hinojosa Engineering
- Construction Manager-at-Risk
 - E-Con Construction, Inc.
- Construction Cost Limitation (CCL)
 - \$650,000
- Program Scope
 - 164 Parking Spaces
 - Drives and Sidewalks

Motions October 6, 2015 Page 23, 10/2/2015 @ 9:04 AM

- Infrastructure Improvements
- Truck Driving Pad
- Landscaping and Irrigation
- Grading

Funding Source

The current Construction Cost Limitation (CCL) is \$650,000 and will be adjusted once the Guaranteed Maximum Price (GMP) proposals have been submitted by the Construction Manager-at-Risk to be presented to the Board for approval. Bond funds are budgeted in the Bond Construction budget for fiscal year 2015-2016.

Reviewers

The proposed schematic design has been reviewed by Broaddus & Associates and staff from Facilities Planning & Construction, Operations and Maintenance, Administration, Technology Resources departments, and Campus Coordinator.


Enclosed Documents

Hinojosa Engineering has developed a schematic presentation describing the proposed design. Enclosed are drawings of the site plans.

Presenters

Hinojosa Engineering has developed a schematic presentation describing the proposed design. Representatives from Broaddus & Associates and Hinojosa Engineering will be present at the Facilities Committee meeting to present the schematic design of the proposed parking and site improvements.

It is requested that the Facilities Committee recommend for Board approval at the October 27, 2015 Board meeting, the proposed schematic design by Hinojosa Engineering for the 2013 Bond Construction Technology Campus Parking and Site Improvements project as presented.







ASPHALT SIDEWALKS CONCRETE DRIVES FUTURE EXPANSIONS SITE PLAN



HINOJOSA ENGINEERING, INC.








AND SITE IMPROVEMENTS

W. MILITARY HIGHWAY



HINOJOSA ENGINEERING, INC.





LEGEND













ENLARGED
TRUCK DRIVING
SCHOOL PARKING



HINOJOSA ENGINEERING, INC.









HINOJOSA ENGINEERING, INC.

Review and Recommend Action on Schematic Design of the 2013 Bond Construction Nursing & Allied Health Campus Parking and Site Improvements

Approval of schematic design by R. Gutierrez Engineering for the 2013 Bond Construction Nursing & Allied Health Campus Parking and Site Improvements project will be requested at the October 27, 2015 Board meeting.

Purpose

Schematic design is the first phase of basic design services provided by the project design team. In this phase, the design team prepares schematic drawings based on the Owner's project program and design meetings with staff. The approval of this phase is necessary to establish the basis on which the project design team is given authorization to proceed with design development and construction document phases.

Justification

Once schematic design is approved, R. Gutierrez Engineering will proceed to prepare all necessary design development drawings and specifications in preparation for the construction documents phase using STC design standards as well as all applicable codes and ordinances. The phases of a construction project are as follows: 1.) Schematic Design, 2.) Design Development, 3.) Construction Documents, 4.) Guaranteed Maximum Price, 5.) Construction, and 6.) Closeout

The Construction Manager-at-Risk provides preconstruction services during the design processes leading to the construction phase. A Guaranteed Maximum Price (GMP) will then be developed and will be presented to the Facilities Committee for review at a future date.

Background

As previously authorized by the Board of Trustees, R. Gutierrez Engineering began working with Broaddus & Associates, Facilities Planning & Construction, and STC staff to develop parking and site plans. The proposed Nursing & Allied Health Campus Parking and Site Improvements project is part of the 2013 Bond Construction Program and includes the following scope:

- > Engineer
 - R. Gutierrez Engineering
- Construction Manager-at-Risk
 - D. Wilson Construction Company
- Construction Cost Limitation (CCL)
 - \$1,100,000
- Program Scope
 - 179 Parking Spaces
 - Drives ,Sidewalks, Student Drop Off Area

Motions October 6, 2015 Page 26, 10/2/2015 @ 9:04 AM

- Infrastructure Improvements
- Landscaping and Irrigation
- Grading

Funding Source

The current Construction Cost Limitation (CCL) is \$1,100,000 and will be adjusted once the Guaranteed Maximum Price (GMP) proposals have been submitted by the Construction Manager-at-Risk to be presented to the Board for approval. Bond funds are budgeted in the Bond Construction budget for fiscal year 2015-2016.

Reviewers

The proposed schematic design has been reviewed by Broaddus & Associates and staff from Facilities Planning & Construction, Operations and Maintenance, Administration, Technology Resources departments, and Campus Coordinator.

Enclosed Documents

R. Gutierrez Engineering has developed a schematic presentation describing the proposed design. Enclosed are drawings of the site plans.

Presenters


R. Gutierrez Engineering has developed a schematic presentation describing the proposed design. Representatives from Broaddus & Associates and R. Gutierrez Engineering will be present at the Facilities Committee meeting to present the schematic design of the proposed parking and site improvements.


It is requested that the Facilities Committee recommend for Board approval at the October 27, 2015 Board meeting, the proposed schematic design by R. Gutierrez Engineering for the 2013 Bond Construction Nursing & Allied Health Campus Parking and Site Improvements project as presented.





NURSING AND ALLIED HEALTH CAMPUS EXPANSION





Motions October 6, 2015 Page 28, 10/2/2015 @ 9:04 AM

Review and Recommend Action on Update for Schematic Design of the 2013 Bond Construction Exterior Elevations of the Pecan Campus South Academic Building

At the August 25, 2015 Board meeting, the Board of Trustees approved schematic design floor plans and asked Boultinghouse Simpson Gates Architects to present revised exterior elevations of the Pecan Campus South Academic Building to the Facilities Committee for Board approval.

The Facilities Committee is asked to recommend Board approval at the October 27, 2015 Regular Board meeting, the revised exterior elevations of the Pecan Campus South Academic Building project as presented.

Presenters

Boultinghouse Simpson Gates Architects has developed a presentation on the revised exterior elevations. Representatives from Broaddus & Associates and Boultinghouse Simpson Gates Architects will be present at the Facilities Committee meeting to present the proposed revised elevations.


It is requested that the Facilities Committee recommend Board approval at the October 27, 2015 Board meeting, the revised exterior elevations of the 2013 Bond Construction Pecan Campus South Academic Building project as presented.



CADEMIC

BUILDING








CADEMIC

Building







CADEMIC

BUILDING










CADEMIC

Building







CADEMIC

Building








South

ACADEMIC

BUILDING







CADEMIC

Building








CADEMIC

BUILDING








CADEMIC

BUILDING








CADEMIC

BUILDING











CADEMIC

BUILDING





Review and Recommend Action on Update for Schematic Design of the 2013 Bond Construction Exterior Elevations of the Pecan Campus STEM Building

At the August 25, 2015 Board meeting, the Board of Trustees approved schematic design floor plans and asked Boultinghouse Simpson Gates Architects to present revised exterior elevations of the Pecan Campus STEM Building to the Facilities Committee for Board approval.

The Facilities Committee is asked to recommend Board approval at the October 27, 2015 Regular Board meeting, the revised exterior elevations of the Pecan Campus STEM Building project as presented.

Presenters

Boultinghouse Simpson Gates Architects has developed a revised presentation of the exterior elevations. Representatives from Broaddus & Associates and Boultinghouse Simpson Gates Architects will be present at the Facilities Committee meeting to present the proposed revised elevations.

It is requested that the Facilities Committee recommend Board approval at the October 27, 2015 Board meeting, the revised exterior elevations of the 2013 Bond Construction Pecan Campus STEM Building project as presented.



ECHNOLOGY

NGINEERING

MATH



QUINCE AVE **SPORTS** FIELD 31st ST. 9 MORTH PECAN CAMPUS WEST DRIV NORTH PECAN CAMP PECAN BOULEVARD OHITE THE BUILDING CONTRACTOR OF THE CONTRACTOR DHIRTH HARMED BRITAIN AND D STEM E G PB-3 PB-4 DHHHE! PB-5 บันทั้ง เรียบของของเกลากาสาราการา PB-12 PB-13 11 10 PB-14 PB-15



PROPOSED PARKING



COVERED STEM MALL SOUTH **BUILDING PROPOSED ACADEMIC** PARKING **BUILDING ECHNOLOGY** NGINEERING COOLING MALL **TOWERS PORTABLE** BUILDING **EXISTING PARKING** OCTOBER 6TH 2015

MALL 📑





ECHNOLOGY

NGINEERING

MATH










ECHNOLOGY

NGINEERING

MATH







ECHNOLOGY

NGINEERING







ECHNOLOGY

NGINEERING







ECHNOLOGY

NGINEERING









ECHNOLOGY

NGINEERING








ECHNOLOGY

E NGINEERING

MATH







ECHNOLOGY

NGINEERING








ECHNOLOGY

NGINEERING







ECHNOLOGY

NGINEERING







ECHNOLOGY

NGINEERING








ECHNOLOGY

NGINEERING

MATH












ECHNOLOGY

NGINEERING

MATH





Review and Recommend Action on Contracting Civil Engineering Services for the Non-Bond Pecan Plaza Parking Area for Police Vehicles

Approval to contract civil engineering design services for the Non-Bond Pecan Plaza Parking Area for Police Vehicles will be requested at the October 27, 2015 Board meeting.

Purpose

The procurement of a civil engineer will provide for design services necessary for the non-bond Pecan Plaza Parking Area for Police Vehicles project.

Justification

The procurement of a civil engineer will allow for the engineer to work with staff to prepare all necessary design development drawings and specifications in preparation for the construction documents phase using STC design standards as well as all applicable codes and ordinances. Construction documents will then be issued for solicitation of construction proposals. Once received, construction proposals will be evaluated and submitted to the Board of Trustees with a recommendation to award a construction contract.

Background

The police department currently has police vehicles that need to be parked and stored in a secured area. STC staff has proposed an area adjacent to the existing police department that could be used for this purpose. The attached site plan shows the proposed location.

In order to proceed with the design of the parking area, staff recommends contracting civil engineering services for preparation of plans and specifications.

Four civil engineering firms listed below were previously approved by the Board at the March 31, 2015 Board meeting for one year to provide professional services as needed for projects under \$500,000.

- 1. Halff Associates, Inc.
- 2. Melden & Hunt
- 3. Perez Consulting Engineering
- 4. R. Gutierrez Engineering

Based on the following criteria, R. Gutierrez Engineers is recommended to provide civil engineering services for this project.

Criteria:

- Previous experience with facilities at Pecan Plaza
- Experience with similar projects
- Familiarity with the college's standards

Funding Source


Funds are available in the FY 2015 – 2016 construction budget for design and construction of these improvements, with the final engineering fees to be negotiated.

		Project Budget
Budget Components	Amount Budgeted	Actual Cost
Design	\$25,000	Actual design fees are estimated and will be finalized during contract negotiations.
Construction	\$250,000	Actual cost will be determined after the solicitation of construction proposals.

Enclosed Documents

Enclosed is a site plan indicating the location of the proposed parking area.

It is requested that the Facilities Committee recommend for Board approval at the October 27, 2015 Board meeting, the contracting of civil engineering services with R. Gutierrez Engineers for the Non-Bond Pecan Plaza Parking Area for Police Vehicles project as presented.



Review and Recommend Action on Schematic Design of the Non-Bond Pecan Campus Student Support Services Building K Student Enrollment Center

Approval of schematic design by Boultinghouse Simpson Gates Architects for the Non-Bond Pecan Campus Student Support Services Building K Student Enrollment Center will be requested at the October 27, 2015 Board meeting.

Purpose

Schematic design is the first phase of basic design services provided by the project design team. In this phase, the design team prepares schematic drawings based on the Owner's project program and design meetings with staff. The approval of this phase is necessary to establish the basis on which the project design team is given authorization to proceed with design development and construction document phases.

Justification

Once schematic design is approved, Boultinghouse Simpson Gates Architects will proceed to prepare all necessary design development drawings and specifications in preparation for the construction documents phase using STC design standards as well as all applicable codes and ordinances. Construction documents will then be issued for solicitation of construction proposals. Once received, construction proposals will be evaluated and submitted to the Board of Trustees with a recommendation to award a construction contract.

Background

Due to the growth in enrollment, the college has experienced large increases in student traffic in Pecan Campus Student Support Services Building (K) particularly during peak registration periods. The redesign will maximize space in order to provide excellent and efficient customer service to each student and ensure all complete the enrollment process. In addition, students will be able to complete the entire enrollment process with staff assistance in one location without moving around between difference offices or other computer labs on campus. Services will be open and transparent providing a warm, welcoming and service-oriented environment and students will be able to remain in the same location with full access to staff for assistance at all times.

At the October 28th, 2014 Board meeting, the Board selected Boultinghouse Simpson Gates Architects from the college's approved list of architectural firms for on-call services. The list of architects for on-call services was approved by the Board on June 26, 2014. At that time, firms were selected in alphabetical order and Boultinghouse Simpson Gates Architects was selected for this project.

Boultinghouse Simpson Gates Architects began working with Facilities Planning & Construction and STC staff to develop plans and interior elevations. The proposed Pecan Campus Student Support Services Building Improvements project includes the following scope:

Motions October 6, 2015 Page 36, 10/2/2015 @ 9:04 AM

> Student Admissions

- Admissions
- Welcome Center
- Information

Funding Source

As part of the FY 2015-2016 non-bond construction budget, funds in the amount of \$400,000 were budgeted for this project. The design team met with staff to review the project scope and developed a schematic design. The architect had originally prepared a preliminary construction cost estimate of \$450,000 based on the schematic design and verifying the existing building conditions. The architect has since then revisited the scope and reduced the construction cost estimate to approximately \$400,000. The total project cost including design and soft costs is \$701,825.

Reviewers

The proposed schematic design has been reviewed by staff from Facilities Planning & Construction, Student Affairs and Enrollment, Operations and Maintenance, Instructional Technologies, and Technology Resources departments, and Coordinated Operations Council.

Enclosed Documents

Boultinghouse Simpson Gates Architects has developed a schematic presentation describing the proposed design. Enclosed are drawings of the site plan, floor plan, and interior views.

Presenters

Boultinghouse Simpson Gates Architects has developed a schematic presentation describing the proposed design. Representatives from Boultinghouse Simpson Gates Architects will be present at the Facilities Committee meeting to present the schematic design of the proposed improvement project.

It is requested that the Facilities Committee recommend for Board approval at the October 27, 2015 Board meeting, the proposed schematic design of the Pecan Campus Student Support Services Building K Student Enrollment Center project as presented.





BUILDING 'K' STUDENT ENROLLMENT CENTER

October 6. 2015




BUILDING

ENROLLMENT CENTER

October 6, 2015





BUILDING 'K' - STUDENT ENROLLMENT CENTER






BUILDING K ENROLLMENT CENTER

October 6, 2015





BUILDING 'K' - STUDENT ENROLLMENT CENTER

ENLARGED COMMON PLAZA PLAN


SCALE: 3/32" = 1'-0"



BUILDING K ENROLLMENT CENTER


October 6, 2015





FLOOR PLAN














October 6, 2015



INTERIOR PERSPECTIVE FROM ENROLLMENT CENTER TOWARDS THE INFORMATION STATION

Enrollment Center Photos – Building "K"

East view toward Admissions



View from entry at Welcome Center




Enrollment Center Photos – Building "K"

West view at corridor to Admissions



Information Center



Review and Recommend Action on Approval of Change Order for the Non-Bond Pecan Campus Portable Buildings Infrastructure

Approval of proposed Change Order No. 2 with Celso Construction for the Pecan Campus Portable Buildings Infrastructure project will be requested at the October 27, 2015 Board meeting.

On April 28, 2015, the Board approved the construction proposal from Celso Construction which included the infrastructure for ten (10) portable buildings. On July 28th 2015, the Board approved the revised plan for relocation of two additional portable buildings for a grand total of twelve (12) portable buildings on the Pecan Campus to allow for the construction of the Bond projects. The two additional portable buildings were required to provide additional classrooms space.

Change Order No. 2 is needed to provide infrastructure for the two additional portable buildings as approved in the revised plan for the relocation of portable buildings.

This proposed change order item has been reviewed and confirmed by the project design team at Melden & Hunt and STC staff.

		Pecan Campus Portable Buildings In	frastructure	
Change Order No.		Item Description and Justification	Cost/ Days	Funding Source
2	•	Description: Infrastructure for electrical, fire alarm, data, mechanical, and concrete sidewalks.	\$40,754.63	Non-Bond Construction
Total Ch	ang	ge Order No. 2	\$40,754.63 0 days	Non-Bond Construction

A representative from Melden & Hunt and STC staff will attend the October 6, 2015 Facilities Committee meeting to respond to questions from the Facilities Committee members.

It is requested that the Facilities Committee recommend for Board approval at the October 27, 2015 Board meeting, proposed Change Order No. 2 in the amount of 40,754.63 with Celso Construction for the Pecan Campus Portable Buildings Infrastructure project as presented.

Review and Recommend Action on Substantial or Final Completion for the Following Non-Bond Construction Projects

Approval of substantial completion for the following projects will be requested at the October 27, 2015 Board meeting:

	Projects	Substantial Completion	Final Completion	Documents Attached
1.	Nursing & Allied Health Campus Irrigation System Upgrade	Recommended	Expected November 2015	Substantial Completion Certificate
	Engineer: SSP Design			
	Contractor: Southern			
	Landscapes			
2.	•	Approved	Recommended	Certificate of
	Drive and Sidewalk	September		Construction
		2015		Completion
	Engineer: R. Gutierrez			·
	Engineering			
	Contractor: Roth Excavating			

1. Nursing & Allied Health Campus Irrigation System Upgrade

It is recommended that substantial completion for this project with Southern Landscapes be approved.

SSP Design and STC staff visited the site and developed a construction punch list. As a result of this site visit and observation of the completed work, a Certificate of Substantial Completion for the project was certified on September 23, 2015. Substantial Completion was accomplished within the time allowed in the Owner/Contractor agreement for this project. A copy of the Substantial Completion Certificate is attached.

Contractor Southern Landscapes will continue working on the punch list items identified and will have thirty (30) days to complete before final completion can be recommended for approval. It is anticipated that final acceptance of this project will be recommended for approval at the November 2015 Board meeting.

2. Pecan Campus AECHS Service Drive and Sidewalk

It is recommended that final completion and release of final payment for this project with Roth Excavating be approved.

Final Completion including punch list items were accomplished as required in the Owner/Contractor agreement for this project. It is recommended that final completion and release of final payment for this project with Roth Excavating be approved. The original cost approved for this project was in the amount of \$49,472.

The following chart summarizes the above information:

Construction Budget	Approved Proposal Amount	Net Total Change Orders	Final Project Cost	Previous Amount Paid	Remaining Balance
\$60,000	\$49,472	\$0	\$49,472	\$46,998.40	\$2,473.60

On August 27, 2015, STC Planning & Construction Department staff along with R. Gutierrez Engineering inspected the site to confirm that all punch list items were completed. Attached is a certificate of construction completion from R. Gutierrez Engineering acknowledging all work is complete and recommending release of final payment.

It is recommended that the Facilities Committee recommend for Board approval at the October 27, 2015 Board meeting, the substantial or final completion of the projects as presented.



September 23, 2015

Mr. Jon Klement

President

Valley Garden Center, Inc. DBA Southern Landscapes

821 E. Beech Ave. McAllen, TX 78501

RE: Substantial Completion

STC Nursing and Allied Health Campus Irrigation Improvements

RFP: 14-15-1080

Dear Mr. Klement:

Please accept this letter as your notice of substantial completion on September 23, 2015 per our walkthrough that day at 4:30. Please note your warranty period on the irrigation ends on September 23, 2016.

This warranty includes the irrigation components installed, backflow, controllers, valves, etc. (Repairs and replacements shall be completed within two weeks of notification from owner).

Two pending items remain first please submit close out documents, warranty letters, laminated colored zoning diagrams, operational manuals and as-built drawings for review. Second the Plug in Relays are a warranty items that require to be addressed.

Please call if you have any questions.

Sincerely,

S. Scott Pajeski, Director

SSP Design, LLC

CERTIFICATE OF CONSTRUCTION COMPLETION

THIS IS TO CERTIFY THAT ON <u>27th</u> DAY OF <u>August 2015</u>, A FINAL INSPECTION was made of the project herein described:

CONTRACT

CO	NTRACT DATE: August 27, 2015
OW	NER: South Texas College
COI	NSTRUCTION CONTRACTOR: Roth Excavating, Inc.
OF	THE CITY OF <u>PHARR, STATE OF TEXAS</u>
	PROJECT DESCRIPTION
CON	NSTRUCTION OF: STC Achieve Early College High School Service Drive and Sidewalk
STC	CONTRACT NO.: Project No. 14-15-1063
LOC	CATED IN OR NEAR THE CITY OF: McAllen, Texas
THIS	S IS TO CERTIFY:
1.	That the work has been completed in accordance with the plans and specifications and all addenda, change orders, supplemental agreements thereto, and with the following exceptions: None
2.	That the sum of <u>zero dollars and 00 /100 dollars</u> (\$ 0.00), be deducted from the final payment of the Contractor for liquidated damages.
3.	That the contractor has presented a "Certificate of Release" stating under oath, that all claims arising out of the performance of work have been fulfilled, and the OWNER is released from all claims arising under or by virtue of said contract.
4.	That the CONTRACTOR has presented in behalf of itself and its sureties, satisfactory evidence that it is bound to repair, replace, and make good any faulty workmanship and/or

contract.

materials discovered in the work within a period of one year from this date, as provided in said

ount of Contract nt of earned to date ous payments deductions	<u> </u>	49,472.00 49,472.00 49,472.00 46,998.40 2,473.60 0.00 2,473.60
al payment in the amount of \$ <u>]</u> ents (<u>\$2,473.60</u>) is now due an	wo Thous d payable	sand Four Hundred Seventy-Three Dollars Engineer's Signature Ramiro Gutierrez, PE
:		CONCURRED BY:
Jef.		n Texas College
	Original Contract fount of Contract int of earned to date ous payments deductions OF FINAL PAYMENT all payment in the amount of \$ 1 is now due an inc.	int of earned to date ous payments deductions OF FINAL PAYMENT all payment in the amount of \$ Two Thousents (\$2,473.60) is now due and payable inc. South BY:

Update on Status of Non-Bond Construction Projects

The Facilities Planning & Construction staff prepared the attached design and construction update. This update summarizes the status of each capital improvement project currently in progress. Mary Elizondo and Rick de la Garza will be present to respond to questions and address concerns of the committee.

At the September 22, 2015 board meeting, staff was authorized to negotiate the final completion and close out of the Technology Campus Cooling Tower Replacement with Pro Tech Mechanical. A delay in the completion of this project may result in possible liquidated damages being incurred. The contractor has been working on completing all pending items needed to close out the project but there is one item that has yet to be addressed. This item could also affect the liquidated damages provision in the contract. Therefore, a recommendation is not being provided at this time but an appropriate recommendation will be provided at a subsequent Facilities Committee meeting.

Project Proj																					
Concept Dependent Comparison of Part			Project	Devel	орте		Des	ign Př	ıase	Sol	icitatic 'opos:	on of als		Const	ruction	on Pha	ıse	Pr	oject nager		Contractor
Robert ECV Architects	Project number	PROJECT DESCRIPTION			Concept Development	Schematic Approval						Construction Start	30%	20%	%9 <i>L</i>			rinai Compietion			
Robert ECV Architects		Pecan Campus and Pecan Plaza																			
Robert R	15-1-002a	Pecan - Covered Area for Ceramic Arts Kilns																Ř		EGV Architects	Holchemont Ltd.
Robert Soulinghouse Simpson Cales Architects John DRE Engineering John DRE Engineering John DRE Engineering John Make Ma	15-1-002b	Pecan - Interior Renovation for Ceramic Arts																R		EGV Architects	Herrcon
John Der Engineering	15-1-006	Pecan - Library Study Rooms Additions						_										R		Boultinghouse Simpson Gates Architects	TBD
Mileton Bulleton Bu	15-1-007	Pecan - Student Activities Sports Field Lighting																Ť		DBR Engineering	Zitro Electric
Rick Boulingbouse Simpson Cales Architects NuA N	15-1-012	Pecan - Infrastructure for Relocation of Portable Buildings																Ť		Melden & Hunt	Celso Construction
NA NA NA NA NA NA NA NA	15-1-013	Pecan - Relocation of Electrical Power Lines																R		Sigma Engineering	Metro Electric
MA MA MA MA MA MA MA MA	15-1-017	Pecan - Building K Enrollment Center																٠-		Boultinghouse Simpson Gates Architects	TBD
NIVA	15-1-020	Pecan - AECHS Service Drive and Sidewalk				A/A												Ť		R. Gutierrez Engineering	Roth Excavation
Rick TBD	16-1-xx1	Pecan - Removal of Existing Trees	N/A	N/A		A/A												Ť		TBD	TBD
Nich	16-1-R01	Pecan - Building A Sign Replacement (RR)]				\dashv	-		J							$\frac{1}{2}$			
Nid Nid	15-1-003	Pecan Plaza - Emergency Generator and Wiring		1	_	1	+	\dashv	4	4			1	1		1	\dashv	-		TBD	TBD
Ni/A	15-1-R04	Pecan Plaza - Resurfacing Back Side of Building B (RR)														1	-	>		Halff Associates	5 Star Construction
Ni/A	16-1-016	Pecan Plaza - Parking Area for Police Vehicles															-	>		TBD	TBD
Ni/A		Mid Valley Campus																			
Robert RoFA	16-2-R07	MV - Childcare Center Play Ground Flooring (RR)	N/A	N/A		A/A	N/A N/	A N	A N/									>		N/A	TBD
Robert R		Technology Campus																			
Robert Ropert Ropert Ropert Ropert Ropert Ropert Ropert Amrech Building Sciences	15-3-004	TC - Building B Doors and Frame Replacement																R		ROFA	TBD
Rick Amfect Building Sciences Rick Halff Associates Rick Ni	15-3-014	TC - Workforce Building Conference Room																Ř		ROFA	TBD
A	13-3-R002	TC - West Academic Building Re-Roofing (RR)																Ř		Amtech Building Sciences	Rio Roofing
A John SSP Design A NVA NVA NVA A NVA NVA	14-3-R004	TC - Cooling Tower Replacement (RR)															\dashv			Halff Associates	Pro-Tech
A		Nursing and Allied Health Campus	-				ŀ	ļ							ı		-	_			_
	14-4-R004	NAH - Irrigation System Upgrade (RR)	N/A N/A															Ť		SSP Design	333
Robert Dannenbaum Engineering Robert Robert Dannenbaum Engineering Robert Rober	16-4-xx4	NAH - Thermal Plant																			
Robert Dannenbaum Engineering Robert Rober		Starr County Campus																			
A N/A N/A N/A Richest Dannenbaum Engineering Robert Dannenbaum Engineering Rick N/A	15-5-xx5	Starr - Building E & J Crisis Mgt Center Generator						_													
Robert Dannenbaum Engineering Robert Dannenbaum Engineering Robert Dannenbaum Engineering Robert Das Engineering Robert Robert		District Wide Improvements																			
A N/A N/A N/A N/A N/A N/A N/A N/A	14-6-010	DW - Building to Building ADA Compliance Ph II														-		- K		Dannenbaum Engineering	TBD
A N/A N/A </td <td>14-6-R012</td> <td>DW - Lighting Upgrades for Parking Lots (RR)</td> <td></td> <td>R</td> <td></td> <td>DBR Engineering</td> <td>Metro Electric</td>	14-6-R012	DW - Lighting Upgrades for Parking Lots (RR)																R		DBR Engineering	Metro Electric
A NVA Rick NVA	15-6-001	DW - Outdoor Furniture	N/A	N/A		N/A	H	H						Ħ		H	H	4		N/A	
	15-6-002	DW - Directional Signage	N/A	Ν				_									_			N/A	TRD

Status of Non-Bond Construction Projects in Progress October 2015

Project	% Complete	Date to Complete		Current Activity	Budget	Contract Amount	Amount Paid	Balance
				Pecan Campus				
Covered Area for Ceramic Arts Kilns	%9	October 2015	4	Construction Phase Construction in progress	\$325,000	\$339,259	0\$	\$339,259
Interior Renovation for Ceramic Arts	%56	August 2015	1.	Construction phase Substantial Completion	\$325,000	\$109,209	\$103,748.55	\$5,460.45
Library Additional Study Rooms	15%	June 2015	- 2	Design phase Design on hold	\$54,000	TBD	\$0	TBD
Sports Fields Lighting	30%	December 2015	- . ~.	Construction phase Construction in progress	\$200,000	\$228,000	0\$	\$228,000
Infrastructure for Relocation of Portable Buildings	20%	December 2015	-, 2	Construction Phase Construction in progress	\$350,000	\$333,249.50	\$76,639.85	\$256,609.95
Relocation of Electrical Power Lines	30%	December 2015	- 2	Construction Phase Construction in progress	\$220,000	\$210,478	\$	\$210,478
Student Services Building K Enrollment Center	%36	October 2015	က် က	Design Phase Design in progress	\$30,000	\$23,125	\$4,990	\$18,135
AECHS Service Drive and Sidewalk Relocation	100%	August 2015	-, 2,	Construction phase Final Completion	\$60,000	\$49,472	\$46,998.40	\$2,473.60
Removal of Trees for Bond Construction	%56	January 2016	- 2.	Design Phase Bids in progress	\$21,000	TBD	\$0	TBD
Building A Sign Replacement	%0	February 2016	-, 2	Project Development Design in progress	\$10,000	TBD	0\$	TBD

Project	% Complete	Date to Complete		Current Activity	Budget	Contract Amount	Amount Paid	Balance
Pecan Plaza Police Department Emergency Generator	%0	May 2016	7.	Project Development Work in progress	\$400,000	TBD	0\$	TBD
Pecan Plaza Asphalt Resurfacing on Alley Side	%52	November 2015	- 2	Construction Phase Construction in progress	\$30,000	\$58,000	\$0	\$58,000
Pecan Plaza Parking Area for Police Vehicles	%0	May 2016	7. 2	Project Development Work in progress	\$250,000	TBD	0\$	TBD
				Mid Valley Campus				
Childcare Center Play Ground Flooring	%56	December 2015	- 2	Design Phase Bidding in progress	\$31,000	TBD	0\$	TBD
				Technology Campus				
West Academic Building Re-roofing	%5/	December 2015	1.	Construction Phase Construction in progress	\$1,698,900	\$1,296,000	\$845,737.50	\$450,262.50
HVAC Cooling Tower Replacement	%56	October 2015	-, 2	Construction Phase Construction in progress	\$415,000	\$396,000	\$361,000	\$35,000
Building B Main Door and Frame Replacement	10%	March 2016	-, 2,	Design Phase Design in progress	\$7,500	\$3,750	0\$	\$3,750
Building C Conference Room Addition	10%	March 2016	- . 4	Design Phase Design in progress	009'6\$	\$4,500	\$0	\$4,500
				Nursing and Allied Health Campus	snd			

Project	% Complete	Date to Complete		Current Activity	Budget	Contract Amount	Amount Paid	Balance
Irrigation System upgrades	%56	October 2015	7.	Construction Phase Substantial Completion	\$30,000	\$37,767	\$26,412.36	\$11,354.64
Thermal Plant	%0	March 2016	- 2	Project Development Solicitation of consultant	\$2,650,000	TBD	\$0	TBD
				Starr County Campus				
Bldg E & J Crisis Management Center with Generator	%0	March 2016	1.	Project Development Work in progress	\$400,000	TBD	\$0	\$400,000
				District Wide				
Building to Building ADA Accessibility Improvements Phase II	%56	October 2015	1.	Design Phase Solicitation of proposals	\$60,000	\$83,389.03	\$68,232.81	\$15,156.22
Parking Lots Lighting Upgrades to LED	%56	August 2015	1.	Construction phase Substantial Completion	\$100,000	\$50,691	0\$	\$50,691
Directional Signage Updates	%01	December 2015	1.	Project development Work in progress	\$50,000	TBD	0\$	TBD
Outdoor Furniture	%56	November 2015	1.	Design phase Solicitation of proposals	\$25,000	TBD	0\$	TBD
For FY 2014-2015, 24 non-bond projects are currently	on-bond proje	cts are currer	ıtly i	in progress, 1 has been completed and 47 pending startup - 72 Total	l 47 pending star	tup - 72 Total		